


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Comanche County, Sec. 35 Twp. 32S Rge. 18W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW1/4  
Lease Owner Continental Oil Company  
Lease Name Peppard Well No. 1  
Office Address P. O. Box 267 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 2-11-64 19  
Plugging completed 2-20-64 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well PBL856 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	5/6	None
				5 1/2	None	3/21

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar.

Rigged up jacks. Sanded to 4820' with 5 sacks of cement.

Shot well at 3800'. Working pipe. Shot at 3700'. Working pipe.  
Shot at 3518'. Working pipe.

Working pipe. Pulling pipe.

Pulling pipe. Plugging well at 300'. Build 18' rock bridge with  
35 sacks of cement. Mudded to 30' with 15 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1964

02-28-1964

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc. CONSERVATION DIVISION  
Address P. O. Box 221 Great Bend, Kansas Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27 day of February, 1964

My commission expires May 27, 1964

Notary Public.

15-033-00091-00-00

PEPPERD-CARTHRAE GAS UNIT #1  
 1980' from the South and 1980' from  
 the West lines of Section 35-T32S-R18W  
 Commanche County, Kansas

Rigged up Rotary Tools 12/29/62

Ran 16 Jts. (580, 40') 10 3/4" Casing. Set @ 546' w/ 425 sacks Common Cement w/ 2% cc. Cement circulated.

Ran 178 Jts. (5723') 5 1/2" 14# New Casing. Set @ 5723' w/ 200 sacks of Salt Saturated Cement.

Tore Down Rotary Tools 1/27/63

FORMATION	FROM	TO
Clay	0	40'
Red Beds, Shells & Sand Streaks	40	210'
Red Beds & Shells	210	560'
Shale & Shells	560	576'
Red Beds & Shells	576	1510'
Shells	1510	2100'
Shale & Shells	2100	2281'
Lime & Shale	2281	2700'
Lime	2700	2791'
Lime & Shale	2791	2835'
Lime	2835	2972'
Lime & Shale	2972	3217'
Lime	3217	3394'
Lime & Shale	3394	3690'
Lime	3690	4228'
Lime, Shale & Sand	4228	4400'
Lime & Shale	4400	4537'
Lime	4537	5192'
Lime W/ Chert Streaks	5192	5255'
Lime	5255	5320'
Lime W/ Chert Streaks	5320	5362'
Lime	5362	5680'
Lime & Chert	5680	5711'
Lime	5711	5762'
Lime & Sand	5762	5806' TD

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 23 1964

CONSERVATION DIVISION  
 Wichita, Kansas

01-23-1964

STATE OF KANSAS

COUNTY OF SEDGWICK

I, Don S. Packer, do hereby certify that the foregoing is true and correct to the best of my knowledge and belief.



*Don S. Packer*  
 \_\_\_\_\_  
 Don S. Packer

Subscribed and sworn to before me this 29th day of January, 1963.

*Helen Y. Langston*  
 \_\_\_\_\_  
 Helen Y. Langston, Notary Public



My Commission Expires:  
 March 26, 1963

