


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Commanche County. Sec. 35 Twp. 32 Rge. 17 E/W
Location as "NE/CNW/SW" or footage from lines
SE SE SE

Lease Owner Godsey Earlougher
Lease Name Alley #1 Well No. _____
Office Address Gret Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/ 8/77 _____ 19____
Plugging completed 4/14/77 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5240
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	319	none
				4 1/2"	5239	4037'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4775' and ran 4 sacks cement. Shot pipe at 4500', 4410', 4230', 4040',
pulled 87 joints. Squeezed hole with 3 sacks hulls, 20 sacks gel, released plug and
displaced with 100 sacks 50/50 pøzmix, 2% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1977

4-25-77

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF _____ KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 77

My commission expires _____



Margaret Melcher
Notary Public.

Voyager Petr.

INC.

Wichita, Kansas

COMPLETION REPORT

15-033-20210-0000

LEASE Alley S.35 T.25R 17W LOC. SE-SE-SE
 COUNTY Comanche STATE Kansas FIELD
 ELEV. KB 2014' DF 2011' GL 2006' ZERO to B.
 ROTARY CONTR. Demarc Arly. RIG NO. 2 SPUD 8-12-76
 SUR. CSG 8 5/8" 29" new DEPTH 319' CEMENT CO. Haliburton
 CEMENT 300 5X reg. 3% C.C.
 PROD. CSG 4 1/2" 10.5" new T.D. CSG 5239' ROTARY T.D. 5240 DATE 8-27-76
 SHOE JT. 11.60' FLOAT 5227'
 CEMENT CO. Haliburton CEMENT 150.5x 50-50 Poz-1890 salt
3/4 of 1% CFR-2 - TOP OF CEMENT 4650' by log

CONTR. Perf. 5164-5175 2 per foot DATE
Back R-1 plug at 4955
Perf. - 4709'-4912' and 4895'-4898'
Back R-1 plug at 4842'
Perf. - 4796'-4806' - still open

Top of K.C. - ~~4400~~ 4460'
Top of MIST. - ~~5120~~ 5120'

RECEIVED
 STATE CORPORATION COMMISSION
 APR 11 1977
 4-11-77
 CONSERVATION DIVISION
 Wichita, Kansas

TUBING-
 RODS-
 EQUIPMENT -