

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2075
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15-033-21016-0001

API NUMBER 033-210160000

LEASE NAME York

WELL NUMBER 142

1420 Ft. from S Section Line

1720 Ft. from E Section Line

SEC. 12 TWP. 32 RGE. 17 (S) or (W)

74020 COUNTY Commanche

Date Well Completed 7/11/03

Plugging Commenced 7/7/03

Plugging Completed 7/12/03

RECEIVED
7-31-03
JUL 31 2003
KCC WICHITA

LEASE OPERATOR Spess Oil Company

ADDRESS 200 South Broadway, Cleveland, OK

PHONE(S) (918) 358-5831 OPERATORS LICENSE NO. 32088

Character of Well Gas

(Oil, Gas, D&A, SVD, Input, Water Supply Well)

The plugging proposal was approved on 7/7/03 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 fitted? Yes If not, is well log attached?

Producing Formation Spergen Depth to Top 5086' Bottom 5114' T.O. 5200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Spergen	5086-94			13 3/8"	102	0
	5104-14			8 5/8"	685'	0
				5 1"	5185'	2038'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

RU POH 5050' of rods and tubing RIH to 5100' circ 9.5" mud to surface. Pumped 40 SXS KWM in 200#s of cem @ 5125' POH to 4000' WOC Tagged CEM btm plug @ 4982' POH Layed down tubing. RU " CSG Jacks worked pipe freepointed and shot @ 2038' Layed down Csg. RIH w 2 3/4" to 1000' Pumped 50sxs plug @ POH to 269' Pumped 30sxs plug POH to 400' Pumped 10 sxs to surface. License No. 32088

Address Spess Oil Company
200 South Broadway, Cleveland, Oklahoma 74020

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Spess Oil Company

STATE OF Oklahoma COUNTY OF Pawnee, ss.

Kevin Stouffer KEVIN STOUFFER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Kevin Stouffer


(Address) 200 S. Broadway Cleveland, Ok. 74020

SUBSCRIBED AND SWORN TO before me this 28th day of July, 2003

Janet Ann Wright NOTARY PUBLIC

Commission Expires: June 12, 2005

Commission # 01009786



Form 03-05
Revised 03-05