

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

MAR 29 2002
3-29-02
CONSERVATION DIVISION
WICHITA, KS

Operator: License # 31514
Name: Thoroughbred Associates LLC
Address: 8100 E 22nd St. N. Bldg. 600 Ste. F
City/State/Zip: Wichita, KS 67226
Purchaser: N/A
Operator Contact Person: Robert C.I Patton
Phone: (316) 685-1512
Contractor: Name: Pickrell Drilling Co. Inc.
License: 5123
Wellsite Geologist: Robert Patton
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)
If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____
10-22-01 11-02-01 01-10-02
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 033-21,272 - 0000
County: Comanche
150 SE ^C SE SE Sec. 16 Twp. 32 S. R. 19 East West
585' feet from S N (circle one) Line of Section
585 feet from E W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Big Red Well #: 1
Field Name: _____
Producing Formation: Viola
Elevation: Ground: 2013.4 Kelly Bushing: 2019.1
Total Depth: 5950 Plug Back Total Depth: LTD 5948
Amount of Surface Pipe Set and Cemented at 735 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.


Drilling Fluid Management Plan ALT 1 5-22-02
(Data must be collected from the Reserve Pit) DPW
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Managing Partner Date: _____
Robert C. Patton
Subscribed and sworn to before me this 20 day of March,
19 2002
Notary Public: [Signature]
Date Commission Expires: September 5, 2004

KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes No Date: 4-10-02 DPW
 Wireline Log Received
 Geologist Report Received
 UIC Distribution



K-033-21272-0000

Slide Two

Operator Name: Thoroughbred Associates LLC Lease Name: Big Red Well #: 1
 Sec. 16 Twp. 32 S. R. 19 East West County: Comanche

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: See attached - <u>MICRO LOG</u> <u>-CDNL</u> - <u>DFL</u> - <u>Sonic</u> - <u>Band Log</u>	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum See Attached <div style="text-align: right;"> RECEIVED KANSAS CORPORATION COMMISSION MAR 29 2002 <u>3-29-02</u> CONSERVATION DIVISION WICHITA, KS </div>
---	---

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	see attached	8 5/8" 23#	735'	250 SX CT 150 CL, A	250	
Conductor		see attached	20#	90'	CLASS A		
Production	7 7/8"	see attached	5 1/2" 15.5#	5945	AFC	300 SX	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	5829-5836	250 gls 15% MCA	
4	reperf. 5830-5834	spot 6 bbls condensate; spot 200 gls	
		7-1/2% Acid; 250 gls 15% HCL	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2-7/8"	5833'	N/A	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr.			Producing Method		
N/A			<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas METHOD OF COMPLETION Production Interval

Vented Sold Used on Lease
 Open Hole Perf. Dually Comp. Commingled
(If vented, Sumit ACO-18.)
 Other (Specify) _____

Attachment to ACO-1

OPERATOR: Thoroughbred Associates, LLC
LEASE NAME: Big Red #1
LOCATION: 150' SE, C, SE SE, 585' FSL 585' FEL
Sec. 16-T32S-R19W
Comanche, County, Kansas
API# : 15-033-212720000

List of all E. Logs Run:

Sonic Log
Dual Induction Log
Compensated Neutron Density
Micro Log
Dual Receiver

Casing Record:

Conductor: set 90' of 20#, cmt w/190 sxs Class A, 3% cc.

Surface: Drilled 12-1/4"; set 8-5/8", 23# surface at 735'KB, cmt w/250 sxs Lite, 3% cc w/1/4# FC/sx, followed by 150 sx Class A, 2% gel, 3% cc.

Production: New 5-1/2" 15.5# prod. Casing set a 5945'. Cmt w/300 sxs of AFC w/5# KC/sx & 1/4# FC/sx in RH, 10 sxs in MH of 60-40 pozmix, 6% gel.

Attachment to ACO-1

OPERATOR: Thoroughbred Associates, LLC
LEASE NAME: Big Red #1
LOCATION: 150' SE, C, SE, 585 FSL 585 FEL
Sec. 16-T32S-R19W
Comanche, County, Kansas
API# 15-033-212720000

LOG TOPS

Heebner	4240'-2221
Brown Lime	4460'-2441
Lansing	4472'-2453
Stark	4770'-2751
Swope	4778'-2759
Hushpuckney	4845'-2826
Cherokee	5069'-3050
Mississippi	5156'-3137
Cowley	5403'-3384
Viola-Dolomite	5829'-3810
RTD	
LTD	5932'-3913

ALLIED CEMENTING CO., INC.

08852

RECEIVED
KANSAS CORPORATION COMMISSION

15-033-21272-0000

Federal Tax I.D. # 29-22000

TO P.O. BOX 31
RUSSELL, KANSAS 67665

3-27-07
CONSERVATION DIVISION
WICHITA, KS

SERVICE POINT:
Medicine Lodge

DATE <u>10-03-01</u>	SEC <u>16</u>	TWP <u>32</u>	RANGE <u>19W</u>	CALLED OUT <u>1:30 AM</u>	ON LOCATION <u>3:45 AM</u>	JOB START <u>12:30</u>	JOB FINISH <u>12:55 pm</u>
LEASE <u>Big Red</u>	WELL #	LOCATION <u>Coldwater Car Wash</u>			COUNTY <u>Comanche</u>	STATE <u>Ks,</u>	
OLD OR NEW (Circle one)		<u>BW 3/4 S, W/S</u>					

CONTRACTOR <u>Pickrell Drilling</u>	OWNER <u>Thoroughbred + Assoc.</u>
TYPE OF JOB <u>Surface</u>	
HOLE SIZE <u>12 1/4</u>	T.D. <u>735'</u>
CASING SIZE <u>8 7/8 x 23"</u>	DEPTH <u>735'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <u>450</u>	MINIMUM <u>-</u>
MEAS. LINE	SHOE JOINT <u>35-24</u>
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>45 Bbls Freshwater</u>	

EQUIPMENT

PUMP TRUCK # <u>265</u>	CEMENTER <u>Carl Balding</u>
BULK TRUCK # <u>359</u>	HELPER <u>Mike Rucker</u>
BULK TRUCK #	DRIVER <u>Eric Holmes</u>
BULK TRUCK #	DRIVER

CEMENT			
AMOUNT ORDERED			
<u>250 SX 65:35:6 + 3/4 cc + 1/4 Flo-seal</u>			
<u>150 SX Class A + 3/4 cc + 2/4 gel</u>			
COMMON <u>150</u>	@ <u>6.65</u>	<u>997.50</u>	
POZMIX	@		
GEL <u>3</u>	@ <u>10.00</u>	<u>30.00</u>	
CHLORIDE <u>13</u>	@ <u>30.00</u>	<u>390.00</u>	
<u>AKW 250</u>	@ <u>6.00</u>	<u>1500.00</u>	
<u>FIO-SEAL 63#</u>	@ <u>1.40</u>	<u>88.20</u>	
	@		
	@		
	@		
HANDLING <u>429</u>	@ <u>1.10</u>	<u>471.90</u>	
MILEAGE <u>429 x 44</u>	<u>.04</u>	<u>755.04</u>	
			TOTAL <u>4232.64</u>

REMARKS:

Run casing + Break circulation,
Pump 5 Bbls freshwater,
Mix 250 SX 65:35:6 + 3/4 cc + 1/4 Flo-seal
+ 150 SX Class A + 3/4 cc + 2/4 gel
Release plug + Displace with 45 Bbls
Freshwater Pump plug + Shut in,
circulated cement ✓

SERVICE

DEPTH OF JOB <u>735'</u>		
PUMP TRUCK CHARGE <u>0-300'</u>		<u>520.00</u>
EXTRA FOOTAGE <u>435'</u>	@ <u>.50</u>	<u>217.50</u>
MILEAGE <u>44</u>	@ <u>3.00</u>	<u>132.00</u>
PLUG <u>Rubber 8 7/8"</u>	@ <u>100.00</u>	<u>100.00</u>
	@	
	@	
TOTAL <u>969.50</u>		

CHARGE TO: Thoroughbred + ASSOC.
STREET _____
CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

<u>1-Baffle Plate</u>	@ <u>45.00</u>	<u>45.00</u>
<u>1-Basket</u>	@ <u>180.00</u>	<u>180.00</u>
	@	
	@	
	@	
TOTAL <u>225.00</u>		

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Mike Kern

TAX _____
TOTAL CHARGE 5427.14
DISCOUNT 542.72 IF PAID IN 30 DAYS
4884.42
Mike Kern
PRINTED NAME

15-033-21272-0000 ALLIED CEMENTING CO., INC.

08933

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <u>12-22-01</u>	SEC <u>16</u>	TWP. <u>32s</u>	RANGE <u>19w</u>	CALLED OUT <u>7:00 Am</u>	ON LOCATION <u>7:45 Am</u>	JOB START <u>8:30 Am</u>	JOB FINISH <u>11:30 Am</u>
LEASE <u>3 1/2 ac</u>		WELL # <u>1</u>	LOCATION <u>Coldwater Car Wash</u>		COUNTY <u>Comanche</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR <input type="radio"/> NEW (Circle one)			<u>3E 1S 1/2</u>				

CONTRACTOR Clarke well service

TYPE OF JOB Squeeze

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 7/8 DEPTH 5765

DRILL PIPE _____ DEPTH _____

TOOL packer DEPTH 5765

PRES. MAX 2000 MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 25 Bbls Saltwater

OWNER Thoroughbred + Assoc

CEMENT AMOUNT ORDERED
50 sx Class H
7# F1-10

COMMON <u>H 50</u>	@ <u>8.20</u>	<u>410.00</u>
POZMIX _____	@ _____	_____
GEL _____	@ _____	_____
CHLORIDE _____	@ _____	_____
<u>F1-10 7#</u>	@ <u>8.00</u>	<u>56.00</u>
_____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____
HANDLING <u>50</u>	@ <u>1.10</u>	<u>55.00</u>
MILEAGE <u>50 - 100</u>	@ _____	<u>100.00</u>
TOTAL		<u>621.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Carl Balding

302 HELPER Steve Davis

BULK TRUCK

364 DRIVER Eric Brewer

BULK TRUCK

_____ DRIVER _____

MAR 29 2002
3-29-02
CONSERVATION DIVISION
WICHITA, KS

REMARKS:

Test plug casing 5836'
perts 5829-36, packer 5765'
Load Hole + circulate oil, test Annulus to 500 psi,
inj rate 2 BPM - 1500 psi, packer released pump
25 sx H+003 1/2 F1-10 + 25 sx H neat displace
is all set packer, pump 10 more displacement
+ squeeze to 2000 psi, release pressure, release packer, squeeze manifold
Reverse out with 45 Bbls, pull 5 stands set packer
+ shut in w/ 1000 psi

SERVICE

DEPTH OF JOB 5836

PUMP TRUCK CHARGE _____ 1428.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 44 @ 3.00 132.00

PLUG _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 1635.00

CHARGE TO: Thoroughbred + Assoc

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX 144.38

TOTAL CHARGE 2400.38

DISCOUNT 225.60 IF PAID IN 30 DAYS

SIGNATURE Alan Vratel

PRINTED NAME Alan Vratel

ALLIED CEMENTING CO., INC.

08708

Federal Tax I.D.# 48-0727860

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine L. D.C.

DATE <u>10-20-01</u>	SEC. <u>16</u>	TWP. <u>32S</u>	RANGE <u>19W</u>	CALLED OUT <u>3:00 P.M.</u>	ON LOCATION <u>5:30 P.M.</u>	JOB START <u>6:20</u>	JOB FINISH <u>6:45</u>
LEASE <u>Big Red</u>		WELL # <u>#1</u>	LOCATION <u>Coldwater Carwash</u>		COUNTY <u>Comanche</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)			<u>3W 3/4S W/INTO</u>				

CONTRACTOR Arrow Drfg. Co.
 TYPE OF JOB Conductor
 HOLE SIZE 30 in T.D. 90
 CASING SIZE 20 in DEPTH 90
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 190 MINIMUM 50
 MEAS. LINE _____ SHOE JOINT 15 FT
 CEMENT LEFT IN CSG. 15 FT
 PERFS. _____
 DISPLACEMENT Fresh H₂O 26 3/4 BBL

OWNER Thoroughbred Assoc.
 CEMENT
 AMOUNT ORDERED 225sx Class A" + 3%
CC

COMMON	<u>225</u>	@	<u>6.65</u>	<u>1496.25</u>
POZMIX		@		
GEL		@		
CHLORIDE	<u>8</u>	@	<u>30.00</u>	<u>240.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>233</u>	@	<u>1.10</u>	<u>256.30</u>
MILEAGE	<u>233 x 44</u>		<u>.04</u>	<u>410.08</u>

EQUIPMENT
 PUMP TRUCK CEMENTER David W.
 # 265 HELPER Shane W.
 BULK TRUCK Steve D.
 # 364 DRIVER Eric B.
 BULK TRUCK _____
 # _____ DRIVER _____

RECEIVED
 KANSAS CORPORATION COMMISSION
3-29-02
 MAR 29 2002

TOTAL 2402.63

REMARKS:

SERVICE

Pipe on bottom break circ
pump 225sx A" + 3% CC
Displace w/ Fresh H₂O
shutt in
Cement did circ

CONSERVATION DIVISION
 WICHITA, KS

DEPTH OF JOB	<u>90</u>		
PUMP TRUCK CHARGE			<u>520.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>44</u>	@	<u>3.00</u> <u>132.00</u>
PLUG		@	
		@	
		@	

TOTAL 652.00

CHARGE TO: Thoroughbred Assoc.
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX	
TOTAL CHARGE	<u>3054.63</u>
DISCOUNT	<u>305.47</u> IF PAID IN 30 DAYS
	<u>2749.16</u>

SIGNATURE D. Woodruff x D. Woodruff
 PRINTED NAME _____

ALLIED CEMENTING CO., INC.

08611

Federal Tax I.D.# 48-0727860

OFFICE P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT
Yee Lodge

DATE <i>11-4-01</i>	SEC. <i>16e</i>	TWP. <i>36.5</i>	RANGE <i>19W</i>	CALLED OUT <i>9:30 AM</i>	OFF LOCATION <i>1100 PM</i>	JOB START <i>5:30 PM</i>	JOB FINISH <i>10:30 PM</i>
LEAS <i>Big Red #1</i>	WELL # <i>1</i>	LOCATION <i>Coldwater Carwash</i>		COUNTY <i>Comanche</i>	STATE <i>KS</i>		
OLD OR NEW (Circle one)			<i>3 W to White House 3/5 1/2</i>				

CONTRACTOR *Pickrell #21*

TYPE OF JOB *Production*

HOLE SIZE *2 7/8* T.D. *5950*

CASING SIZE *5 1/2 x 5.5* DEPTH *5947*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL *latchdown Lnscri* DEPTH *5926*

PRES. MAX *1700* MINIMUM *200*

MEAS. LINE SHOE JOINT *21*

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT *142 BBLs 2% KCL water*

OWNER *Thoroughbred Assoc.*

CEMENT

AMOUNT ORDERED *25 5x 60.40 lb for Mud Mouse 300 sx ASC #5 #kol seal 2 1/4 # 70 seal # 600 #1-10*

COMMON	<i>15</i>	@ <i>6.65</i>	<i>99.75</i>
POZMIX	<i>10</i>	@ <i>3.55</i>	<i>35.50</i>
GEL FL-10	<i>169 #</i>	@ <i>8.00</i>	<i>1352.00</i>
CHLORIDE	<i>1</i>	@ <i>10.00</i>	<i>10.00</i>
Mud Clean	<i>500 gal</i>	@ <i>.75</i>	<i>375.00</i>
Clapra	<i>15 gals</i>	@ <i>22.90</i>	<i>343.50</i>
ASC	<i>300</i>	@ <i>8.50</i>	<i>2550.00</i>
KOL SEAL	<i>1500 #</i>	@ <i>.50</i>	<i>750.00</i>
FL-10 SEAL	<i>75 #</i>	@ <i>1.40</i>	<i>105.00</i>
HANDLING	<i>410</i>	@ <i>1.10</i>	<i>451.00</i>
MILEAGE	<i>410 x 44</i>	@ <i>.04</i>	<i>172.60</i>
TOTAL			<i>6773.35</i>

EQUIPMENT

PUMP TRUCK CEMENTER *Justin Hart*

352 HELPER *David Felio*

BULK TRUCK

359-251 DRIVER *Eric Holmes*

BULK TRUCK

DRIVER

REMARKS:

SERVICE

*Pipe on Bottom Drop Ball Break Circ
Plug 12 BBLs Mud Clean + 5 BBLs
Fresh H₂O Plug mouse 15x 60.40 lb
Plug Rat 15 sx 60.40 lb
Mix 300 sx ASC @ 14.5 # - 84 BBLs
Release Plug Disp 142 BBLs at
2% KCL water Bump plug 1700 # to
1700 # Release press float hold*

DEPTH OF JOB	<i>5950</i>	
PUMP TRUCK CHARGE		<i>1428.00</i>
EXTRA FOOTAGE	@	
MILEAGE	<i>44</i>	@ <i>3.00</i> <i>132.00</i>
PLUG	@	
	@	
	@	
TOTAL		<i>1560.00</i>

CHARGE TO: *Thoroughbred Assoc.*

STREET

CITY *RUSSELL* ZIP

KANSAS CORPORATION COMMISSION

FLAT EQUIPMENT

<i>5 1/2 AFLL Float Shoe</i>		<i>265.00</i>
<i>latchdown Plug</i>	@ <i>350.00</i>	<i>350.00</i>
<i>2 Baskets</i>	@ <i>128.00</i>	<i>256.00</i>
<i>8 Centralizers</i>	@ <i>400.00</i>	<i>400.00</i>
	@	
	@	
TOTAL		<i>1269.00</i>

MAR 29 2002
3-29-02

To Allied Cementing CONSERVATION DIVISION
You are hereby requested to return cementing equipment
and furnish cementer and helper to assist owner or
contractor to do work as is listed. The above work was
done to satisfaction and supervision of owner agent or
contractor. I have read & understand the "TERMS AND
CONDITIONS" listed on the reverse side.

TAX

TOTAL CHARGE *9622.35*

DISCOUNT *962.24* IF PAID IN 30 DAYS

3660.11

SWAMPY MARSH

PRINTED NAME

SIGNATURE *[Signature]*