

CP

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 - 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Co.

Complete Address: Box 2585 Amarillo, TX

Lease Name: Ora Baker Well No. 2

Location: 600ft FEL & 1843ft FSL Sec. 23 Twp. 33s Rge. 20 (E)(W) W

County: Comanche Total Depth 4820 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

361 ft of 13 3/8 surface pipe cemented with 600 sacks. Set
plug at 4790 ft, 20 sacks cement. Fill hole to 410 ft,
plug, 75 sacks cement. Mud to 35 ft, plug, 1/2 sack hulls,
20 sacks cement to surface. 2 sacks cement in rat hole.

Very truly yours,

A. Russell Birstein
Conservation Division Agent