

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 14 1963
 1-14-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. John Hill of Continental Oil Co. has this

date requested permission to plug the following described well:

Mr. John Hill guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: P. O. Box 494, Medicine Lodge, Kansas

Lease Name: SHIMER Well No. B 1
Shriver

Location: C - NE - NE Sec. 18 Twp. 33S Rge. 16 (E) (W) W

County Comanche Total Depth 5060 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

390' of 10³/₄" surface pipe, 994' of 8 5/8" surface pipe.

fill hole with heavy mud to 270', 1/4 sack hulls and 1st

cementing plug set at 270' with 25 sacks cement, fill

hole with heavy mud to 40', 1/4 sack hulls, 2nd cementing

plug and 15 sacks of cement to base cellar. Rat hole

bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent