



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1982  
1-26-82  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Elmo Morgenstern of Clark Oilfield Service has this date requested permission to plug the following described well:

Operator's Full Name: F. X. O. Production Corp.

Complete Address 200 W. Douglas St. 300 Wichita Kansas 67202

Lease Name: Jellison "A" Well No. 1

Location: C-SW-SW-SW Sec. 4 Twp. 33S Rge. 19W (E) (W)

County: Comanche Total Depth: 5500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Morgenstern was instructed to plug the well as follows:

There is 627' of 8 1/2" surface pipe cement circulated. They ran + cemented 5490' of 4 1/2" production pipe. They perforations toped at 5133'. 1st plug sanded off bottom hole with 4 sbys of cement on top bringing top of plug to 5066'. 2nd plug they pumped in 5 sbys Jell 5 sbys hulls released rubber plug and pumped 200 sbys of cement on top of it. They recovered 3660' of 4 1/2" production pipe. The plugging was accomplished by Allied cementing. The cement used was common cement.

Very truly yours,

Paul Luth  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1982

CONSERVATION DIVISION  
Wichita, Kansas