

KANSAS

SL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-151-10882-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robert L. Austin

Complete Address Box 159 Stafford, Ks

Lease Name Harrell Well No. 8

Location SE/SE/SE Sec. 36 Twp. 26 Rge. 13 (E) (W) X

County Pratt Total Depth 4320

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 3:00 PM Day 6 Month 1 Year 1972

The above well was plugged as follows:

432 ft 8 5/8 surface pipe cemented with 250 sacks. 4319 ft 5 1/2 long
string cemented with 125 sacks. Top perf. 3872 ft. Sand back to
3850 ft, 5 sacks cement with bailer. Pulled 2330 ft 5 1/2. Pump
2 sacks hulls, 15 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed *W. Russell*
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4988-W