

15-151-10875-00-00

CPB  
R

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 2-34 County: Pratt

Location: S/2 SW Sec. 36 Twp. 26 Rge. 13 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4342

I have this date completed supervision of plugging of:

Lease Name: Beck "E" Well No. 1

Operator's Full Name: The Bradford Companies

Complete Address: Box 346, Tulsa, Oklahoma.

Plugging Contractor: Wilson Inc.

Address: Stafford, Kaus. License No. 375

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5 PM Day 26 Month Dec. Year 58

The above well was plugged as follows:

437' of 8 5/8" surface casing circulated with cement. Open end pro-  
duction. Hole was filled with sand to 4315 and 5 sack cement dumped  
with dump bailer. Pipe ripped and 11 jts pulled. 50 sack weight and  
fell mud pumped and circulated. Pipe pulled. Hole filled to 300'  
with mud. 10' rock bridge set at 300' and 20 sack cement dumped to p  
bridge. Heavy mud to 40'. 10' rock bridge set at 40' and 10 sack cement  
dumped to base of cellar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
12-30-58  
DEC 30 1958  
CONSERVATION DIVISION  
Wichita, Kansas  
PLUGGING  
FILE SEC 36 T 26 R 13W  
BOOK PAGE 2 LINE 34