

*JK*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-151-10885-00-00

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name H & H Supply Company

Complete Address: Box 94173, Oklahoma City, Oklahoma

Lease Name Harrel "A" Well No. # 7

Location NW SE SE Sec. 36 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4362'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Gayle E. Toland, Pipe Contractor

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 2:00 PM Day 30th Month June Year 1965

The Above well was plugged as follows:

433' of 8 5/8" surface pipe, cement circulated. 4362' of 5 1/2" long string,  
cemented with 175 sacks. Plug was pushed to 3850', and 10' of rock bridge,  
and cemented with 5 sacks. 2638' of 5 1/2" long string was recovered from the  
hole. Hole was squeezed. 22 bbls. of heavy drilling mud and 121 sacks of  
cement was pumped into the surface pipe, through an 8 5/8" swage, to a  
pressure of 100 lbs. This cement was pumped by Gayle E Toland, Pipe  
Contractor.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 1 1965  
7-1-65

Signed: Archie Elving  
Well Plugging Supervisor

DATE 7/1/65

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 1396-W