

<sup>10</sup>  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-151-10886-00-00

RECEIVED  
STATE CORPORATION COMMISSION

APR 30 1965  
4-30-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name H & H Supply Company

Complete Address: Box 94173, Oklahoma City, Oklahoma

Lease Name Harrel "A" Well No. # 4

Location SW NE SE Sec. 36 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4327'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 9:15 AM Day 29th Month April Year 1965

The Above well was plugged as follows:

466' of 8 5/8" surface pipe, cemented with 250 sacks. 4327' of 5 1/2"  
long string, cemented with 250 sacks. Plug back to 4278'. Top perforation  
4236'. Bottom of the hole was sanded to 4225', and cemented with 5 sacks.  
1810' of 5 1/2" long string was recovered from the hole. Fluid was up in the  
hole. Bridge plug was pushed in fluid to 300', and 10' of rock. 5 sacks of  
cement was mixed in barrel and put on plug at 290', through the dump bailer,  
and let set over-night. Next morning hole was bailed dry, and 20 sacks of  
cement was added to the plug. Hole was filled with mud to 40', and 10' of  
rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/30/65

INV. NO. 1080-W

Signed: Archie Elving  
Well Plugging Supervisor