

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**  
**15-151-10881-00-00**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name H & H Supply Company

Complete Address: Box 94173, Oklahoma City, Oklahoma

Lease Name Harrel "A" Well No. # 9

Location E/2 NE SE Sec. 36 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4318'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Galye E. Toland, Pipe Contractor

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 2:30PM Day 29th Month June Year 1965

The Above well was plugged as follows:

440' of 8 5/8" surface pipe, cemented with 300 sacks. 4318' of 5 1/2" long  
string, cemented with 125 sacks. Plug back to 4280'. Top perferation 4232'.  
Plug was pushed to 4230', and 25' rock bridge, and cemented with 5 sacks.  
Pipe parted and 794' of 5 1/2" long string was recovered from the hole. 20 bbls.  
of drilling mud was pumped into 5 1/2" at 350', and 35 sacks of cement was  
pumped into 5 1/2" at 260'. Fluid in the hole was bailed down to 40', and 10'  
of rock bridge, and cemented with 10 sacks to the base of the cellar.

**RECEIVED**

I hereby certify that the ~~above well~~ <sup>above well</sup> was plugged as herein stated.

**INVOICED**

DATE 7/1/65

INV. NO. 1397-W

JUL 1 1965  
7-1-65  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Archie Elving  
Well Plugging Supervisor