

KANSAS

Form CP-3
Rev. 6-1-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-6-76
DEC 06 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -033 -00206 -00-00 (of this well)

Operator's Full Name Patton Oil Co
Complete Address Suite 200 5660 S. Syracuse Circle Englewood, CO
Lease Name Schutte A Well No. 1
Location C NE Sec. 10 Twp. 32 Rge. 16 (E) (W) W
County Comanche Total Depth 4736
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Both Casing Pulling Co
Address 715 S. A Arkansas City, KS License No. 684
Operation Completed: Hour 11:00 AM Day 2 Month 12 Year 1976

The above well was plugged as follows:

40 ft 13 3/8 surface cement circulated. 348 ft 8 5/8 surface
cemented with 300 sacks. 4732 ft 5 1/2 long string cemented with 125 sacks
Open hole. Sand to 4700 ft, 5 sacks cement with bailer. Pulled 3150
ft 5 1/2. Set 10 ft rock bridge at 240 ft with 25 sacks cement. Mud to
30 ft, plug, 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell R. Christensen
Well Plugging Supervisor

DATE 12-6-76
INV. NO. 4272-W