

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-033-30060-00-00

OCT 27 1964
10-27-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Livingston Oil Company

Complete Address: Box 1797, Tulsa 1, Oklahoma

Lease Name Victory Life Well No. # 1

Location C SE NW Sec. 2 Twp. 32 Rge. 18 (E) (W) W

County Comanche Total Depth 6117

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling Company

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 12:45 PM Day 26th Month Oct. Year 1964

The Above well was plugged as follows:

628' of 10 3/4" surface pipe, cemented with 600 sacks. 5338' of 5 1/2" long
string, cemented with 220 sacks. Cast iron bridge plug was set above all
perforations, set at 4600', and cemented with 5 sacks. Bridge plug was set
on fluid level at 340', and 20' of rock bridge, bringing the top of the
plug to 320'. 10 3/4" surface pipe was filled with 6 yards of ready-mix
cement, from 320' to the base of the cellar.

4331' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/29/64

INV. NO. 50-W