

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033- 20185-00-01

245 North Water
Wichita, KS 67202

Operator's Full Name The Roxana Corporation

Complete Address Box 1162 Great Bend, Kansas

Lease Name Reynolds Well No. #1

Location C SW NW Sec. 28 Twp. 32 Rge. 18W (East) (West)

County Comanche Total Depth 5378'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 12:00P Day 5 Month 2 Year 1981

The above well was plugged as follows:

502' - 8 5/8" csg w/ 350 sx cement

4 1/2" csg set @ 5310' Plug back to 5226'

Perfs 5210' to 5200' Sand back w/ bailer to 5175' & 4 sx cement

Plug & 50 sx 50/50 poz 6 1/2 gal @ 800' 15 gel 8 hulls 10 gel

Plug & 40 sx, cement @ 500' Pulled 4000' 4 1/8" csg.

Bridge & 10 sx. @ 40' to 5' below GI

Cemented by Sun SIP 100#

STATE CORPORATION COMMISSION

FEB - 9 1981
02-09-1981
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above well was plugged as herein stated.

4946
3-13 81

Signed: M. V. Bush
Conservation Division Agent