

15-033-00091-00-00

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1964
02-24-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Co.

Complete Address: Box 267, Great Bend, Kansas

Lease Name J. T. Peppard Well No. # 1

Location C NE SW Sec. 35 Twp. 32 Rge. 18 (E) (W) W

County Comanche Total Depth 5806

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 4:00PM Day 20th Month Feb. Year 1964

The Above well was plugged as follows:

546' of 10 3/4" surface pipe, cement circulated. 5723' of 5 1/2" long string,
cemented with 75 sacks. Plug back to 4856', Top perforation 4826'. Bottom
of hole was sanded to 4800', and cemented with 5 sacks. Hole was filled
with mud to 300', plug was set at 300', with 10' rock bridge, and cemented
with 30 sacks. Hole was filled with mud to 40', 10' rock bridge, and cem-
ented with 15 sacks to base cellar.

3400' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/29/64
INV. NO. 8406-u