

15-033-00099-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1964
03-16-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hall-Jones Oil Corporation

Complete Address: 1710 Liberty Bank Bldg., Oklahoma City, Oklahoma

Lease Name Parcel Well No. # 1

Location C SE NW Sec. 36 Twp. 32 Rge. 18 (E) (W)W

County Comanche Total Depth 5663

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling Inc.

Address: 905 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 7:30PM Day 12th Month March Year 1964

The Above well was plugged as follows:

281' of 8 5/8" surface pipe, cemented with 225 sacks. Hole was filled
with drilling mud to 275, 1st cementing plug was bridged solid at 275',
and cemented with 25 sacks. Hole was filled with drilling mud to 40',
2nd cementing plug was bridged solid with hulls at 40', and cemented
with 10 sacks to base cellar. Rat hole bridged and cemented with 5
sacks.

This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/18/64

INV. NO. 8804-w