

15-033-10020-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued March 23, 1967.

APR 7 1967
04-07-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. M. Huber Corporation

Complete Address: 5415 N. Pennsylvania, Oklahoma City, Oklahoma

Lease Name Herd Well No. # 1

Location C NE SW Sec. 16 Twp. 32 Rge. 18 (E) (W) W

County Comanche Total Depth 6016'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Gayle E. Toland & Company

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 11:45AM Day 6th Month April Year 1967

The Above well was plugged as follows:

535' of 13 3/8" surface pipe, cemented with 700 sacks. 5387' of 4 1/2"
long string, cemented with 250 sacks. Cast iron bridge plug set at 4850'.
Top perforation 4727'. 30 sacks of cement was pumped on bottom with the
top of the cement at 4400'. 3217' of 4 1/2" long string was recovered from
the hole. 4 1/2" long string was pulled up to 600', and 25 sacks of Gel-
Mud was pumped at 600'. 4 1/2" was now pulled up to 450', and 50 sacks of
cement was pumped at 450'. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 25 sacks to the base of the cellar.

This cementing was done by Halliburton Cementing Company.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 4/7/67
INV. NO. 5022-W