

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20577-6000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Mega Petroleum Corp. #6465

Complete Address 4925 Greenville, Suite 614, Dallas Texas 75206

Lease Name Todd Well No. 1

Location C-NW-NW Sec. 7 Twp. 33 Rge. 18 (East)(West)

County Comanche Total Depth 6029'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Lawson Drilling Co. Inc. Rig # 244

Address 200 Douglas Bldg, Broadway, Douglas, Wichita, KS 67202 License No. 244

Operation Completed: Hour: 10:30 PM Day: 23 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug at 840' with 70 sks of cement 2nd plug at 440' with 40 sks of cement. 3rd plug on solid bridge 40' to 0' with 10 sks of cement. The cement was pumped through drill pipe with hole full of heavy mud. Then circulated 10 sks of cement in rat hole. The cement used was 50/50 prop mix 4% gel 7.3% cc. The plugging was accomplished by Allied Cementing.

Amount of Surface Casing: 615' of 8 5/8" cement circulated with 325 sks 60/40 2% gel 7.3% cc

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 10-20-82
INV. NO. 1424-W