

15-033-30005-00-00

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

September 12, 1965
SEP 15 1965
09-15-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Magaw & Zimmer

Complete Address: 22 Park Ave. Bl'dg. Oklahoma City Oklahoma.

Lease Name Herd Unit Well No. #1

Location C-NW-SE Sec. 17 Twp. 32S Rge. 18W (E) (W)

County Commanche COMANCHE Total Depth 5845 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert Jones

Address: 514 Orpheum Bl'dg. Wichita Kansas. License No.

Operation Completed: Hour 9:30 AM Day 12 Month Sept. Year 1965

The Above well was plugged as follows:

550 ft. of 8 5/8" surface pipe circulated with cement. Heavy drill mud
to 540 ft. cementing plug, & 1/4 sack hulls. 25 sacks cement, mud to 40 ft.
cementing plug, 1/4 sack hulls, 10 sacks cement to base of cellar.
2 sacks cement in rat-hole & 2 sacks cement in mousehole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/15/65
INV. NO. 1807-W

Signed: Herman Justus
Well Plugging Supervisor