

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20,496-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Wells Energy Corp.

Complete Address 700 S. Colorado Blvd., Suit 454 Denver, Co. 80222

Lease Name Gregg Well No. 1

Location C5W NE1/4 1980' from N Line 1980' E. Line Sec. 26 Twp. 33S Rge. 17W (East) (West)

County Comanche Total Depth 5200'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor H-30 Drilling Inc. Rig #7

Address 151 N. Water - Wichita, Kansas License No. _____

Operation Completed: Hour: 2:00 PM Day: 8 Month: October Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There is 478' of 8 3/8" surface casing cement circulated. The subsurface was topped at 950'. 1st plug circulated heavy mud at 950' then pumped 40 lbs of cement to this level in hole. 2nd plug pushed rubber plug to 450' with 35 lbs of cement pumped on top of rubber plug. 3rd plug 40' to 0' on top of solid bridge with 10 lbs of cement. Then put 10 lbs cement in rat hole & 5 lbs in mouse hole. Plugging accomplished by Dowell Cementing of Pratt, Mo

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11-25-81
INV. NO. 8507-c

Signed: Paul Luth
OCT 9 1981
10-9-81
CONSERVATION DIVISION
Wichita, Kansas