


15-033-00034-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Commanche County. Sec. 25 Twp. 32S Rge. 19W (II) (W)  
Location as "NE/CNW/SW" or footage from lines C-SW-NE  
Lease Owner Aladdin Petroleum Corporation  
Lease Name Herd Well No. 1  
Office Address 809 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed December 4 1959  
Application for plugging filed December 4 1959  
Application for plugging approved December 4 1959  
Plugging commenced December 4 1959  
Plugging completed December 4 1959  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6151 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	* TO	SIZE	PUT IN	PULLED OUT
				13-3/8	398'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Layed down drill pipe.  
Filled hole with heavy mud to 300'  
Set bridge plug and 1/2 sack of hulls and 35 sacks cement  
Filled with mud 35' set bridge plug with 1/2 sack of hulls  
Cemented with 15 sacks cement to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1960  
8-10-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Patton Drilling Company  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
George W. Bruce (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George W. Bruce  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1959  
April 6, 1963  
My commission expires \_\_\_\_\_  
Luella Fickitt Notary Public.



15-033-00034-0000

Aladdin Petroleum Corp.  
B. J. Herd Well #1  
Total Depth 6152'  
Comm. 10/24/59  
Comp. 12/5/59  
Contractor Parron Drilling Co., Inc.

Location SW NE Section 25-732S-R19W  
Comanche County, Kansas.  
CASING RECORD  
13 3/8" Casing at 398'  
Cemented with 450 Sacks Cement

Surface Clay	25
Sand	35
Sandy Clay	115
Red Bed	530
Shale & Shells	850
Red Bed & Shells	1560
Anhydrite & Shale	1825
Lime Shale	2288
Lime	2430
Lime & Shale	2498
Lime	2537
Lime & Shale	4037
Lime & Shale	4080
Sandy Shale & Lime	4103
Sandy Shale	4109
Shale & Sand	4230
Sandy Shale & Lime	4327
Sandy Shale	4384
Douglas Sand	4400
Sandy Shale & Lime	4483
Lime & Shale 4563	4563
Lime	4615
Lime Chalky	4651
Lime	4852
Lime & Shale	4885
Lime	4949
Lime & Shale	5100
Lime	5134
Lime & Shale	5417
Lime	5437
Lime & Shale	5521
Lime	5563
Lime & Shale	5593
Lime	5618
Lime & Shale	5661
Lime	5725
Lime & Shale	5800
Lime & Chert	5898
Cherty Lime Dolomite & Shale	5970
Sand Chalky Lime	
Dolomite & Shale	6038
Sand Dolomite & Lime	6042
Sand Dolomit Lime & Shale	6127
Cherty Lime & Dolomite	
Arb	6152
Total Depth	6152

Measurements from Rotary Bushing  
Rotary Bushing to Ground Level 11 Ft.

Tops	
Miss	5190
Viola	5809
Simpson	5970
Arbuckle	6127

*Jmf*

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1960  
8-10-60  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgewick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PATTON DRILLING COMPANY, INC.

By *R. P. Kendrick*

Subscribed and sworn to before me this 8th day of August 1960

*Geo. F. Johnston*  
Notary Public  
Geo. F. Johnston.

My Commission expires 2-28-64