

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-03320,714-0000

LEASE NAME Lawrence Rich

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Ramco Energy Corporation

SEC. 19 TWP. 32 RGE. 19 (K) or (W)

ADDRESS Box 340, Great Bend, Kansas 67530

COUNTY Commanche

PHONE # (316) 792-1960 OPERATORS LICENSE NO. 3536

Date Well Completed 1988

Character of Well Oil GAS AND WC
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 4-27-92

Plugging Completed 6:00 PM

The plugging proposal was approved on 4-27-92 (date)
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Miss Depth to Top 5129 Bottom 5133 T.D. 5245

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	678	0
				5 1/2	5243	3049

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each.
Bottom plug: Sanded to 5080 & bailed 5 sx cement.

Top plug: Pumped 300 lb Hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lb Hulls, released 8 5/8 wiper plug, & pumped 125 sx of 60/40 6%. Had max pressure of 450 lbs & shut in pressure of 150 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ramco Energy Corporation


STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas 67530



AND SWORN TO before me this 28 day of April

Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

RECEIVED
APR 29 1992
STATE CORPORATION COMMISSION
Wichita, Kansas