

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Comanche County. Sec. 11 Twp. 33S Rge. 18W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____


C-NE/4
Lease Owner William M. Fuller
Lease Name Donald M. Todd Well No. 1
Office Address 2020 Ft. Worth Nat'l. Bank Bldg., Ft. Worth
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

76102
Date Well completed August 12, 1979
Application for plugging filed Verbal Application 19__
Application for plugging approved Verbal Approval 19__
Plugging commenced August 12, 1979
Plugging completed August 12, 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,685'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	63'	None
				8-5/8"	550'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 5,685 ft. (rotary total depth) to 600 ft. Set plug at 600 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 600 ft. to 330 ft. Set plug at 330 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 330 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 2 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss. Dean Britting, Agent (Signature of owner) XXXXXXXXXXXXXXXXXXXX

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1979



Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1979
8-20-79
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY William M. Fuller

SEC. 11 T. 33S R. 18W
LOC. C-NE/4

FARM Donald M. Todd NO. 1

COUNTY Comanche

ROTARY TOTAL DEPTH 5,685'
COMM. July 30, 1979 COMP. August 12, 1979
CONTRACTOR H-30, Inc. (Rig #77)
ISSUED August 17, 1979

CASING
16" Set at 63' cemented w/80sxs cement
10 3/4"
8 5/8" Set at 550' cemented w/400 sxs cement
5 1/2"
4 1/2"

ELEVATION 1,945' GR.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale	171'
Red Bed	794'
Red Red and Sand	2,273'
Lime and Shale	5,138'
Lime	5,242'
Lime and Shale	5,430'
Lime and Chert	5,685'
Rotary Total Depth	5,685'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas)
County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 17th day of August, 1979.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1979
8-20-79
CONSERVATION DIVISION
Wichita, Kansas