


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Comanche County. Sec. 12 Twp. 33S Rge. 18 E/W  
Location as "NE/CNW1/4SW1/4" or footage from lines  
C S/2 of SE/4

Lease Owner Mid-Continent Energy Corporation  
Lease Name Todd Well No. 1  
Office Address 712 One Twenty Building, Wichita 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed 2/19/80 19  
Application for plugging filed 2/19/80 19  
Application for plugging approved 2/19/80 19  
Plugging commenced 2/19/80 19  
Plugging completed 2/19/80 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations. TD 5240'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	253'	13-3/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 700' with 35 sacks  
2nd plug @ 240' with 35 sacks  
3rd plug @ 40' with 35 sacks  
5 sacks in rathole  
Job complete @ 10:30 P.M. 2/19/80

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 3-7-80  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg, Slawson Drilling Co., Inc. (employee of owner) or (owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
James C. Remsberg  
200 Douglas Building, Wichita, 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of March, 19 80

Mary Lou Taylor  
Mary Lou Taylor  
Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Mid-Continent Energy Corporation  
 712 One Twenty Building  
 Wichita, Kansas 67202

LEASE: Todd #1  
 C S/2 of SE/4 Sec. 12-33S-18W  
 Comanche County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: 1/31/80

COMPLETED: 2/19/80

RTD: 5240'

SURFACE CASING: 13-3/8" set at 253' with 300 sx cement

0' to 256' 17 1/2" surface hole  
 256' to 1104' Red Bed  
 1104' to 1218' Shale  
 1218' to 2530' Lime with Shale  
 2530' to 4280' Shale & Lime  
 4280' to 4830' Lime & Shale  
 4830' to 5215' Lime  
 5215' to 5240' Mississippian Lime  
 RTD 5240'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.  
 hereby state the above and foregoing is an accurate copy of the  
 Todd #1 log for Mid-Continent Energy Corporation.

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me this  
 5th day of March, 1980

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

RECEIVED  
 STATE CORPORATION COMMISSION

MAR - 7 1980  
 3-7-80  
 CONSERVATION DIVISION  
 Wichita, Kansas

