


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Comanche County, Sec. 15 Twp. 32S Rge. 17 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
660' FSL & 660' FWL

Lease Owner Cities Service Oil Co.  
Lease Name York "A" Well No. #1  
Office Address 209 E. William, 700 Sutton Place, Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed 3-9-78 19  
Application for plugging filed 3-9-78 19  
Application for plugging approved 3-9-78 19  
Plugging commenced 3-9-78 19  
Plugging completed 3-9-78 19  
Reason for abandonment of well or producing formation  
Commercial quantities of oil not found  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5240'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	203'	None
				(Conductor)		
				8 5/8"	638'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Plug @ 630' w/40 sx. RECEIVED  
Plug @ 40' w/12 sx STATE CORPORATION COMMISSION  
Rat Hole 3 sx.

MAR 22 1978  
3-22-78

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.


STATE OF Kansas COUNTY OF Kansas, ss.

Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God

(Signature)

435 Page Court, 220 W. Douglas, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of March, 19 78



10-4-79

Juanita M. Green

Notary Public.

DRILLER'S LOG

COMPANY: Cities Service Oil Co.

SEC. 15 T. 32S R. 17W

WELL NAME: York "A" #1

LOC. 660' FSL & 660' FWL

COUNTY: Comanche

RIG NO. #3

TOTAL DEPTH 5240'

ELEVATION

COMMENCED: 2-17-78

COMPLETED: 3-9-78

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD: 13 3/8" @ 203' w/200 sx. 50/50 poz., 100 sx. 50/50 poz., 2% cc.

SURFACE: 1-inched top w/200 sx. 50/50 poz., 2% cc. (Conductor).

8 5/8" @ 638' w/400 sx. 50/50 poz., 2% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand & Redbed	393
Sand	1145
Redbed	1383
Redbed & Shale	1612
Shale & Sand	1981
Shale	2335
Shale & Lime	3151
Lime & Shale	4000
Lime	4365
Lime & Shale	4646
Lime	5240
<u>ROTARY TOTAL DEPTH</u>	<u>5240</u>

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1978

3-22-78  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas )

COUNTY OF Sedgwick )

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the  
York "A" #1 well.

Wilson Rains  
Wilson Rains

Subscribed and sworn to before me this 14 day of March, 1978.

My Appointment Expires:

10-4-79

Juanita M. Green  
Juanita M. Green

