


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Comanche County. Sec. 30 Twp. 32S Rge. 17 (W)
Location as "NE/CNW%SW%" or footage from lines SE SW
Lease Owner Parker Petroleum Co., Inc.
Lease Name Cary Well No. 1
Office Address Box 791, Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 21, 1956
Application for plugging filed November 21, 1956
Application for plugging approved November 28, 1956
Plugging commenced November 21, 1956
Plugging completed _____ 19____
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 5902 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	none	4283		13"	345'	None
Douglas Sand	SW	4318		8 5/8	360'	360'
Lansing	""	4447				
Mississippi	none	5135				
Viola	"	5653				
Simpson	"	5764				
Arbuckle	SW	5890				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole up 340' with 30 sacks heavy mud. Filled hole up 20' with 20 sacks cement.
Welded on steel cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert Jones Drilling Company
Address Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Kay, ss.
Charlotte J. Boone (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charlotte J. Boone
Ponca City, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 29 day of January, 19 57

My commission expires December 1, 1959

Francis Fern Is ton Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 30 T. 32 R. 17 W
BOOK PAGE 120 LINE 21

RECEIVED
JAN 31 1957
1-31-57
CONSERVATION DIVISION
Wichita, Kansas

BRETT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLERS WELL LOG

CARY #1
SE SW SECTION 30-32-17 W
COMANCHE COUNTY, KANSAS

COMMENCED 10-9-56
COMPLETED 11-20-56

DEPTH		FORMATION	REMARKS
FROM	TO		
0	30	SURFACE CLAY & SHALE	
30	156	SAND & SHALE	
156	176	SHALE & RED BED	
176	350	RED BED & SHELLS	RAN 350' OF 13 3/8" CASING, CEMENTED @ 345' W/300 BAGS CEMENT.
350	520	RED BED & SHALE	
520	650	LIME, SHELLS & SHALE	
650	1665	SHALE & SHELLS	
1665	1850	SHALE & LIME SHELLS	
1850	2205	SHALE & SHELLS	
2205	2260	LIME	
2260	2320	ANHYDRITE	
2320	2415	ANHYDRITE & SHALE	
2415	2460	LIME	
2460	2478	SHALE & SHELLS	
2478	2505	LIME	RAN 2509' OF 8 5/8" CASING, CEMENTED @ 2504' W/250 BAGS CEMENT.
2505	2895	LIME	
2895	3379	LIME & SHALE	
3379	3511	LIME	
3511	3600	SHALE & LIME	
3611	3640	BROKEN LIME	
3640	3820	LIME & SHALE	
3820	3890	SHALE & SHELLS	
3890	4060	SHALE & LIME	
4060	4195	SHALE	
4195	4350	SHALE & LIME	
4350	4356	SAND	
4356	4430	SANDY SHALE	
4430	4445	LIME	
4445	4505	LIME & SHALE	
4505	4788	LIME	
4788	4841	LIME & SHALE	
4841	4895	LIME	
4895	5135	LIME & SHALE	
5135	5280	LIME	
5280	5322	LIME & SHALE	
5322	5749	LIME	
5749	5765	SAND	
5765	5825	SANDY LIME	
5825	5845	LIME	
5845	5891	SANDY SHALE & SAND	
5891	5902	LIME	
5902	TD		DRY & ABANDONED

RECEIVED
STATE CORPORATION COMMISSION
FEB - 2 1957
2-2-57
CONSERVATION DIVISION
Wichita, Kansas

I H. F. Jones, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE CARY #1.

H. F. Jones

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 24 DAY OF November, 1956 PERSONALLY APPEARED H. F. Jones TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 11-19-58

Sumner S. Hall
NOTARY PUBLIC

PLUGGING
FILE NO. SEC. 30 T. 32 R. 17W
BOOK PAGE 120 LINE 21