

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-033-21199 -00-00

LEASE NAME Brass

WELL NUMBER 2-2

1380 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 2 TWP. 33 RGE. 19 (E) or (W)

COUNTY Comanche

Date Well Completed 04/23/2001

Plugging Commenced 10/14/2002

Plugging Completed 10/15/2002

RECEIVED  
10-29-02  
OCT 29 2002  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Lario Oil & Gas Company

ADDRESS 301 S. Market Street; Wichita, KS 67202

PHONE#( ) 316-265-5611 OPERATORS LICENSE NO. 5214

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07/08/02 (date)

by Kevin Stube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top 5224 Bottom 5260 T.D. 6050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Conductor		0	70	20"	70	None
Surface		0	700	8-5/8"	700	None
Production		0	6039	4-1/2"	6039	3200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

1st Plug: 50 sx cement + 10 sks gel @ 1100'. 2nd Plug: 50 sx @ 730'. 3rd Plug: 30 sx @ 250'

Top Plug: 10 sx @ 40' to surface. Cement is 60/40 Pozmix + 6% gel

Name of Plugging Contractor Pratt Well Service Inc. License No. 5893

Address PO Box 847 Pratt, KS 67124-0847

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lario Oil & Gas Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jay G. Schweikert, Operations Engineer

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jay G. Schweikert

(Address) 301 S. Market Street; Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 28 day of October, 2002

KATHYL FORD  
Notary Public - State of Kansas  
My Appt. Expires 10-22-06

Kathyl S. Ford  
Notary Public

My Commission Expires: 10-22-06

99