


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5190'
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	469'	8 5/8"	11 jts.	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

At 700' 40 sacks cement, @450' 40 sacks cement,
@40' 10 sacks cement, 5 sacks to rat hole.
Job by Halliburton. Plug down @ 10:30 A.M. 8/20/80.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Venture Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
James G. Collins (employee of owner) or ~~(owner or operator)~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James G. Collins
1625 KSB&T Building, Wichita, KS. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of August, 1980

Virginia Lee Smith
Virginia Lee Smith Notary Public.

My commission expires August 25, 1984





August 25, 1980

SUITE 1625 KSB&T BLDG. 125 NORTH MARKET WICHITA, KANSAS 67202 (316) 267-1550

OPERATOR

Griggs Oil, Inc.
Suite 1625 KSB&T Building
Wichita, Kansas 67202

Einsel C-1
C NE Section 24-33S-18W
Comanche County, Kansas

Well Log

0 - 475	Shale
475 - 1050	Shale
1050 - 1567	Shale
1567 - 1748	Shale
1748 - 2270	Shale & Lime
2270 - 2475	Shale
2475 - 2590	Shale & Lime
2590 - 2850	Shale & Lime
2850 - 3070	Shale & Lime
3070 - 3275	Shale & Lime
3275 - 3297	Shale & Lime
3297 - 3346	Shale & Lime
3346 - 3546	Shale & Lime
3546 - 3735	Shale & Lime
3735 - 3872	Shale & Lime
3872 - 4045	Shale & Lime
4045 - 4235	Shale & Lime
4235 - 4423	Shale & Lime
4423 - 4615	Shale & Lime
4615 - 4743	Shale & Lime
4743 - 4864	Shale & Lime
4864 - 4976	Shale & Lime
4976 - 5048	Shale & Lime
5048 - 5105	Shale & Lime
5105 - 5153	Shale & Lime
5153 - 5154	Shale & Lime
5154 - 5175	Shale & Lime
5175 - 5190	Shale & Lime
5190 - TD	

DRILLING CONTRACTOR

Venture Drilling, Inc.
Suite 1625 KSB&T Building
Wichita, Kansas 67202

Commenced: 8/8/80
Completed: 8/20/80

Casing Program

Ran 11 jts. of 8 5/8" 24# used casing.
Set @469', cemented with 350 sacks common,
3% c.c. 2% gel. Plug down @3:15 A.M.

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1980
8-28-80
CONSERVATION DIVISION
Wichita, Kansas

Plugged hole. @700' 400 sks., @450'
40 sks., @40' 10 sks., 5 sks. to rat
hole. Plug down @10:20 A.M. 8/20/80

CERTIFICATION

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss:

I, Virginia Lee Smith of VENTURE DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Virginia Lee Smith
Virginia Lee Smith