

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-20377-00-00

LEASE NAME Knop

WELL NUMBER B-5

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 25 TWP. 26 RGE. 13W (~~E~~or(W))

COUNTY Pratt

Date Well Completed       

Plugging Commenced 10-23-91

Plugging Completed 10-25-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR T G T Petroleum Corporation

ADDRESS 209 E. Williams #615 Wichita, Ks. 67101

PHONE#(316) 262-6489 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on        (date)

by        (KCC District Agent's Name).

Is ACO-1 filed?        If not, is well log attached?       

Producing Formation        Depth to Top        Bottom        T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	457'	none
				4 1/2"	3200'	1744'

RECEIVED  
STATE CORPORATION COMMISSION  
10-31-91  
OCT 31 1991  
DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Sanded bottom to 3100' ran 4 sacks cement. Shot pipe @1835', 1744'  
Pumped 300# hulls, 10 gel, 300 sacks cement followed by 10 gel,  
100# hulls mixed and pumped 100 sacks 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: T G T Petroleum Corporation

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 29 day of October, 1991

*Jane Herzberg*  
Notary Public

My Commission Expires:       



CONTRACTOR'S WELL LOG

15-151-20377-00-00

OPERATOR: TGT Petroleum Co. ✓  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: KNOP "B" #5  
 LOCATION: C NE NE SE, Sec. 25-26S-13W  
 Pratt County, Kansas  
 SPUD DATE: 3-29-77  
 COMPLETION DATE: 4-15-77  
 GEOLOGIST: George Dent

0	268	Sand & Clay
268	757	Shale & Red Bed
757	782	Anhydrite
782	1615	Shale
1615	1870	Shale & Lime
1870	3105	Lime & Shale
3105	3130	Lime
3130	3900	Lime & Shale
3900	3914	Lime
3914	4018	Lime & Shale
4018	4050	Lime
	4050	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 30 1991  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Spud hole at 6:30 p.m. 3-29-77. Drilled 465' of 12 1/4" hole. Drilled 1026' - 7 7/8" hole. Came out of hole. Ran 12 jts. of 8 5/8" surface casing. (Tally 450') Set at 457'. Cemented with 300 sx. of 60/40 posmix, 3% Ca. Cl., 2% gel. Plug was down at 10:30 a.m. 3-30-77.

T.D. 4050', Ran 78 jts. of 4 1/2" casing. Set at 3200'. Cemented with 300 sx. of Halliburton Cement. Plug was down at 11:00 a.m. 4-15-77.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the KNOP "B" #5, C NE NE SE, Section 25-26S-13W, Pratt County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state on this 21st day of April, 1977.

Kathy S. Goertz  
 Kathy S. Goertz, Notary Public



*Handwritten initials*