

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

20471-0000  
 API NUMBER 15-033-47

LEASE NAME Robinson

WELL NUMBER 3

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div. C/  
 office within 30 days.

E2/SE4 Ft. from S Section Line  
NE4 Ft. from E Section Line

LEASE OPERATOR Farrar Pump and Supply

SEC. 5 TWP. 315 RGE. 18 (E) of (W)

ADDRESS Medicine Lodge, Ks. 67104

COUNTY Comanche

PHONE (816) 886-3762 OPERATORS LICENSE NO. 3399

Date Well Completed 7-8-81

Character of Well Oil

Plugging Commenced 9-19-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-28-89

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? X If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 5114

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 22 1989

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	528	450 sxw none
				4 1/2	5110	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
sand from 5080 to 4850 - 4sx cem. dump bailor

5 SK - Cottonseed hulls 105 SK - cement 70 SK - mix 30K - 2% gel  
6 SK - Bentonite gel 70 SK - gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105


Address Box 187 Medicine Lodge, Ks 67104

STATE OF Kansas COUNTY OF Barber, ss.

Farrar Pump & Supply (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) Box 160 + 281 Highway 3



SUBSCRIBED AND SWORN TO before me this 21 day of DECEMBER, 19 89.

Teresa L. Myers  
 Notary Public

My Commission Expires: 11-10-90

KANSAS

Alford Field

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 5 T. 31 R. 18

API No. 15 — COMMANCHE — 15-033-20-471-0000  
County Number

Loc. C E/2 SE/4 NE/4

County COMMANCHE

Operator  
ALTMAN OPERATING COMPANY

Address  
1901 FOURTH NATL BANK BLDG., TULSA, OK 74119

Well No. 3 Lease Name ROBINSON


Footage Location  
710' feet from (X) (S) line 320' feet from (E) (XX) line

Principal Contractor EXPLORATION DRILLING Geologist

Spud Date 4-6-81 Date Completed 7-8-81 Total Depth 5114' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

640 Acres  
N



Locate well correctly

Elev.: Gr. 2145'

DF KB 2153'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/2	8-5/8"	22#	526'	Class A	450	2%gel-3%CaCl
PRODUCTION	7-7/8"	4 1/2"	10.5#	5110'	Class A	125	10% cacl 50/50 5# Gelsonite, 3/4 of 1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3		5060'-5068'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	5047'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/1000 gal 15% MCA	5060-5068'

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1986

4-18-86  
CONSERVATION DIVISION  
Wichita, Kansas

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
8/9/81	Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 8 bbls. Gas TSTM MCF Water 22 bbls. Gas-oil ratio ----- CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)
USED ON LEASE	5060-5068'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **ALTMAN OPERATING COMPANY** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **3** Lease Name **Robinson** Oil

S **5** T **31N** R **18** <sup>XX</sup>  
W

**WELL LOG**  
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Bed	0	1783'		
Anhy & Dolomite	1783'	2127'		
Lime & Shale	2127'	2668'		
Shale	2668'	3420'		
Lime & Shale	3420'	5114'		
TD		5114'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature
	President
	Title
	September 8, 1981
	Date