

RECEIVED

OCT 18 2001  
10-18-01  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

CONFIDENTIAL

Operator: License # 31821  
Name: J-F Oil Company LLC  
Address: 1119 Toulon Ave  
City/State/Zip: Hays, Kansas 67601  
Purchaser:  
Operator Contact Person: Frank Taggart  
Phone: (785) 623-9438  
Contractor: Name: Val Energy Inc.  
License: 5822

Wellsite Geologist: Jon D. Christensen

Designate Type of Completion:  
 New Well  Re-Entry  Workover

Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator:

Well Name:

Original Comp. Date: Original Total Depth:

Deepening  Re-perf.  Conv. to Enhr./SWD

Plug Back  Plug Back Total Depth

Commingled  Docket No.

Dual Completion  Docket No.

Other (SWD or Enhr.?)  Docket No.

08-28-01 09-12-01 09-12-01  
Spud Date or Date Reached TD Completion Date or  
Recompletion Date Recompletion Date

API No. 15 - 033212420000

County: Comanche

C NW SW Sec. 10 Twp. 32 S. R. 20  East  West

2086' feet from (S) N (circle one) Line of Section

540' feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW (SW)

Lease Name: Fellers Well #: 2

Field Name: unnamed

Producing Formation: N/A

Elevation: Ground: 1906' Kelly Bushing: 1911'

Total Depth: 5250 Plug Back Total Depth:

Amount of Surface Pipe Set and Cemented at 903' Feet

Multiple Stage Cementing Collar Used?  Yes  No

If yes, show depth set \_\_\_\_\_ Feet

If Alternate II completion, cement circulated from \_\_\_\_\_

feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

Drilling Fluid Management Plan (Data must be collected from the Reserve Pit)

Chloride content 7400 ppm Fluid volume 1800 bbls

Dewatering method used settlement

Location of fluid disposal if hauled offsite:

Operator Name:

Lease Name: License No.:

Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West

County: \_\_\_\_\_ Docket No.:

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: *Frank Taggart*

Title: Owner/Operator Date: 10-15-01

Subscribed and sworn to before me this 15th day of October

2001

Notary Public: *Nancy Taggart*

Date Commission Expires: 7-2-03

KCC Office Use ONLY

Letter of Confidentiality Attached

If Denied, Yes  Date: \_\_\_\_\_

Wireline Log Received

Geologist Report Received

UIC Distribution

NANCY TAGGART  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 7-2-03

Operator Name: J-F Oil Company LLC Lease Name: Fellers Well #: 2  
 Sec. 10 Twp. 32 S. R. 20  East  West County: Comanche

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No (Attach Additional Sheets)  Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No  Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No  Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Submit Copy)  List All E. Logs Run:  Dual Induction/Dual Compensated Porosity	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%;">Name</td> <td style="width:20%;">Top</td> <td style="width:20%;">Datum</td> </tr> <tr> <td>Heebner Shale</td> <td>4154'</td> <td>-2243</td> </tr> <tr> <td>Lansing</td> <td>4355'</td> <td>-2444</td> </tr> <tr> <td>Marmaton</td> <td>4827'</td> <td>-2916</td> </tr> <tr> <td>Pawnee</td> <td>4909'</td> <td>-2998</td> </tr> <tr> <td>Mississippi</td> <td>5051'</td> <td>-3140</td> </tr> </table>	Name	Top	Datum	Heebner Shale	4154'	-2243	Lansing	4355'	-2444	Marmaton	4827'	-2916	Pawnee	4909'	-2998	Mississippi	5051'	-3140
Name	Top	Datum																	
Heebner Shale	4154'	-2243																	
Lansing	4355'	-2444																	
Marmaton	4827'	-2916																	
Pawnee	4909'	-2998																	
Mississippi	5051'	-3140																	

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Conductor	30"	20"	73#	60'	Grout	71/2yds	
Surface	17 1/2"	13 3/8"	48#	420'	Class A	525	3%cc 2%gel
Surface	12 1/4"	8 5/8"	24#	903'	Class A	350	3%cc 2%gel

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type		Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated		(Amount and Kind of Material Used)	
				Depth

TUBING RECORD		Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr.			Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas  Vented  Sold  Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION  Open Hole  Perf.  Dually Comp.  Commingled  Other (Specify) \_\_\_\_\_

Production Interval \_\_\_\_\_

# ALLIED CEMENTING CO., INC.

8264

Federal Tax I.D.# 48-0727860

APR 02 2003

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

**CONFIDENTIAL ORIGINAL**

From SERVICE POINT: Med Lodge

DATE <u>8-28-01</u>	SEC. <u>10</u>	TWP. <u>S23</u>	RANGE <u>20W</u>	CALLED OUT <u>3:00 PM</u>	ON LOCATION <u>6:30 PM</u>	JOB START <u>5:30 AM</u>	JOB FINISH <u>9:30 AM</u>
LEASE <u>Fellers</u>	WELL # <u>2</u>	LOCATION <u>Coldwater Carwash</u>			COUNTY <u>Comanche</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			9w to Stop Sign <u>1/4 NE</u> into				

CONTRACTOR <u>Val #1</u>	OWNER <u>J-F Oil Co. LLC</u>
TYPE OF JOB <u>Surface</u>	CEMENT
HOLE SIZE <u>17 3/8</u>	T.D. <u>400</u>
CASING SIZE <u>13 3/8 x 48</u>	DEPTH <u>400</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
FOOT <u>Duffle</u>	DEPTH <u>378</u>
PRES. MAX <u>400</u>	MINIMUM <u>150</u>
MEAS. LINE	SHOE JOINT <u>1/2</u>
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>59 BBLs Fresh H<sub>2</sub>O</u>	<u>KCC AW</u>

**EQUIPMENT**

PUMP TRUCK # <u>352</u>	CEMENTER <u>Justin Hart</u>	HELPER <u>David Felio</u>
BULK TRUCK # <u>240</u>	DRIVER <u>Dwayne West</u>	
BULK TRUCK #	DRIVER	

AMOUNT ORDERED <u>275 sx 65.356 + 3/6 cc</u>		
<u>1/4" Flo-seal 100 sx class A +</u>		
<u>3% CL + 2% Coal</u>		
<u>Top off 150 sx class A 3/2</u>		
COMMON A <u>250</u>	@ <u>6.65</u>	<u>1662.50</u>
POZMIX	@	
GEL <u>5</u>	@ <u>10.00</u>	<u>50.00</u>
CHLORIDE <u>18</u>	@ <u>30.00</u>	<u>540.00</u>
<u>FLO-SEAL 69#</u>	@ <u>6.30</u>	<u>1132.50</u>
	@	
	@	
HANDLING <u>562</u>	@ <u>1.10</u>	<u>618.20</u>
MILEAGE <u>562 x 50</u>	<u>.04</u>	<u>1124.00</u>

**RECEIVED**  
OCT 18 2001  
KCC WICHITA SERVICE

**REMARKS:**  
Pipe on Bottom Break Circ  
Mix 275 sx 65.356 @ 12.8# - 97 BBLs  
Mix 100 sx A3/2 @ 15.2# - 24 BBLs  
Release Plug Disp 59 BBLs  
Dump Plug 150# to 300# Shut head  
in Release Press. Did not Circulate  
Cement Top off 150 sx A3/2  
circulated Cement ✓

DEPTH OF JOB <u>400'</u>		
PUMP TRUCK CHARGE <u>0-300'</u>		<u>520.00</u>
EXTRA FOOTAGE <u>120'</u>	@ <u>.50</u>	<u>60.00</u>
MILEAGE <u>50</u>	@ <u>3.00</u>	<u>150.00</u>
PLUG <u>13 3/8 TRP</u>	@ <u>220.00</u>	<u>220.00</u>
	@	
	@	

TOTAL 950.00

CHARGE TO: J-F Oil Co. LLC

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**FLOAT EQUIPMENT**

<u>13 3/8</u>		
<u>1- Duffle Plate</u>	@ <u>85.00</u>	<u>85.00</u>
<u>1- Basket</u>	@ <u>250.00</u>	<u>250.00</u>
<u>1- Guide Shoe</u>	@ <u>310.00</u>	<u>310.00</u>
	@	
	@	

TOTAL 645.00

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE 7418.80

DISCOUNT 7418.80 IF PAID IN 30 DAYS

6676.92

SIGNATURE Dale Smith

PRINTED NAME Dale Smith

# ALLIEL CEMENTING CO., INC.

8322

Federal Tax I.D.# 48-0727860

APR 02 2003

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

CONFIDENTIAL

ORIGINAL SERVICE POINT:  
Confidential  
Medicine Lodge

DATE 8-30-01	SEC. 10	TWP. 32s	RANGE 20w	CALLED OUT 12:00 pm	ON LOCATION 12:30 pm	JOB START 3:00 pm	JOB FINISH 4:00 pm
LEASE Fellers	WELL# 2	LOCATION Caldwellwater car wash			COUNTY Comanche	STATE KS.	
OLD OR NEW (Circle one)		w/ to Blacktop 1/4 in 5/8					

CONTRACTOR \_\_\_\_\_ OWNER JF Oil Co.

TYPE OF JOB Top off

HOLE SIZE 17 1/2 T.D. KCC

CASING SIZE 13 7/8 DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH OCT 15 2001

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH CONFIDENTIAL

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

CEMENT AMOUNT ORDERED \_\_\_\_\_

100 3x A3+2

used 70 3x

COMMON	<u>70</u>	@	<u>6.65</u>	<u>465.50</u>
POZMIX		@		
GEL	<u>2</u>	@	<u>10.00</u>	<u>20.00</u>
CHLORIDE	<u>3</u>	@	<u>30.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>105</u>	@	<u>1.10</u>	<u>115.50</u>
MILEAGE	<u>105 X 50</u>	@	<u>.04</u>	<u>210.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Carl Balding

# 360 HELPER Mike Rucker

BULK TRUCK DRIVER Dwayne West

# 259

BULK TRUCK DRIVER \_\_\_\_\_

RECEIVED TOTAL 901.00

OCT 18 2001 SERVICE

KCC WICHITA

REMARKS:

Run wire line, out side 13 7/8

Casing tag cement - 50'

Run 50' 1 inch + pump 50 3x

Cement, Run 25' 1 inch in Mouse

Hole + pump 20 3x cement

Cement circulate to surface both holes

DEPTH OF JOB 50'

PUMP TRUCK CHARGE \_\_\_\_\_ 580.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 50 @ 3.00 N/C

PLUG \_\_\_\_\_ @ \_\_\_\_\_

2 joints 1 inch @ 20.00 40.00

TOTAL 620.00

CHARGE TO: JF oil Co, LLC.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE 1521.00

DISCOUNT 1521.00 IF PAID IN 30 DAYS

1521.00

SHANE SUMMERS

PRINTED NAME

SIGNATURE \_\_\_\_\_

# ALLIED CEMENTING CO., INC.

8269

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

CONFIDENTIAL ORIGINAL SERVICE POINT: From Mac Lodge  
APR 17 2003  
Confidential

DATE <u>9-5-01</u>	SEC. <u>10</u>	TWP. <u>32S</u>	RANGE <u>20W</u>	CALLED OUT <u>4:30 AM</u>	ON LOCATION <u>7:00 AM</u>	JOB START <u>12:00 PM</u>	JOB FINISH <u>12:45 PM</u>
LEASE <u>Fellers</u>	WELL # <u>2</u>	LOCATION <u>Coldwater Carwash</u>			COUNTY <u>Comanche</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>9 W to Stop Sign 1/4 N E into</u>							

CONTRACTOR Vap #1 OWNER J-F Oil Co. LLC  
 TYPE OF JOB surface **KCC**  
 HOLE SIZE 12 1/4 T.D. 908  
 CASING SIZE 8 7/8 x 24 DEPTH 908 1-5 2001  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH **CONFIDENTIAL**  
 TOOL AFU Insert DEPTH 859  
 PRES. MAX 800 MINIMUM 100  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 45

CEMENT  
 AMOUNT ORDERED 200 sx 65.35 lb + 3% cc  
+ 1/4" Flo-seal 150 sx Class A +  
3% ec + 2% gel

COMMON <u>A</u>	<u>150</u>	@ <u>6.65</u>	<u>997.50</u>
POZMIX		@	
GEL	<u>3</u>	@ <u>10.00</u>	<u>30.00</u>
CHLORIDE	<u>12</u>	@ <u>30.00</u>	<u>360.00</u>
<u>AW</u>	<u>200</u>	@ <u>6.30</u>	<u>1260.00</u>
<u>Flo-Seal 50#</u>		@ <u>1.40</u>	<u>70.00</u>
		@	
		@	
HANDLING	<u>375</u>	@ <u>1.10</u>	<u>412.50</u>
MILEAGE	<u>375</u>	<u>1.50</u>	<u>.04</u>
			<u>750.00</u>

CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 55 BBLs Fresh H<sub>2</sub>O  
**EQUIPMENT**  
 PUMP TRUCK CEMENTER Justin Hart  
 # 375 HELPER Mark Dourgardt  
 BULK TRUCK  
 # 240-251 DRIVER Eric Holmes  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED TOTAL 3880.00

OCT 18 2001  
 SERVICE  
 KCC WICHITA  
 DEPTH OF JOB 908  
 PUMP TRUCK CHARGE 0-300' 520.00  
 EXTRA FOOTAGE 508' @ .50 254.00  
 MILEAGE 50 @ 3.00 150.00  
 PLUG 8 7/8 TRP @ 100.00 100.00  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

TOTAL 1024.00

REMARKS:  
Pipe on Bottom Drop Ball  
Break Circ. Mix 200 sx 65.35 lb  
@ 12.8" - 70 BBLs  
Mix 150 sx Class A 3/2 @ 152# - 24 BBLs  
Release Plug Disp 55 BBLs  
Bump Plug 300# to 800#  
Release Press Float Held  
Circulated Cement ✓

CHARGE TO: J-F Oil Co. LLC  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

8 5/8  
**FLOAT EQUIPMENT**  
AFU Insert @ 325.00 325.00  
Guide Shoe @ 215.00 215.00  
1" Centralizer @ 55.00 55.00  
 @ \_\_\_\_\_  
 @ \_\_\_\_\_

TOTAL 595.00

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE 5499.00  
 DISCOUNT 549.90 IF PAID IN 30 DAYS  
4949.10  
Shane Summers  
 PRINTED NAME

SIGNATURE [Signature]

# ALLIED CEMENTING CO., INC.

8272

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

CONFIDENTIAL

ORIGINAL

APR 02 2003  
Confidential

SERVICE POINT

Mod Lodge

DATE	9-12-01	SEC.	10	TWP.	J25	RANGE	20W	CALLED OUT	11:00 AM	ON LOCATION	2:00 PM	JOB START	3:00 PM	JOB FINISH	5:15 PM	
LEASE	Fellers	WELL #	1#2	LOCATION	Coldwater Carwash				COUNTY	Comanch	STATE	KS				
OLD OR NEW (Circle one)			9W		14N		E into									

CONTRACTOR Val #1  
TYPE OF JOB Rotary Plug  
HOLE SIZE 7 7/8" T.D. 5250  
CASING SIZE 8 3/8" DEPTH 904  
TUBING SIZE DEPTH  
DRILL PIPE 4 1/2 x 16 DEPTH 950  
TOOL DEPTH  
PRES. MAX MINIMUM  
MEAS. LINE SHOE JOINT  
CEMENT LEFT IN CSG.

OWNER J-F Oil Co.  
CEMENT AMOUNT ORDERED 125 BX 20.406

PERFS.  
DISPLACEMENT 105 DBLS Fresh #0 + Mud  
EQUIPMENT

COMMON	A 75	@	6.65	498.75
POZMIX	50	@	3.55	177.50
GEL	7	@	10.00	70.00
CHLORIDE	KCC	@		
		@		
		@		
		@		
		@		
		@		
HANDLING	132	@	1.10	145.20
MILEAGE	132 x .50		.04	264.00

PUMP TRUCK # 352 CEMENTER Justin Hart HELPER David Felio  
BULK TRUCK # 242 DRIVER Eric Brewer  
BULK TRUCK # DRIVER

RECEIVED  
OCT 18 2001  
KCC WICHITA SERVICE  
TOTAL 1155.45

REMARKS:

- 50 SX @ 950'
- 40 SX @ 450
- 10 SX 40'
- 15 SX Rat

DEPTH OF JOB	950			
PUMP TRUCK CHARGE				520.00
EXTRA FOOTAGE		@		
MILEAGE	50	@	3.00	150.00
PLUG		@		
		@		
		@		

CHARGE TO: J-F Oil Co  
STREET  
CITY STATE ZIP

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL				
TAX				
TOTAL CHARGE	1825.45			
DISCOUNT	182.55			
	1642.90			

SIGNATURE *Jeremy Stuckey*

IF PAID IN 30 DAYS  
Jeremy Stuckey  
PRINTED NAME