

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19839-00-00
Spot: SESESE Sec/Twnshp/Rge: 12-22S-10E
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: DEMALORIE Well #: W-39 (78)
County: GREENWOOD Total Vertical Depth: 2183 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	2132		525 SX
SURF	8.625	180		75 SX

Well Type: EOR UIC Docket No: E03423.39 Date/Time to Plug: 05/06/2014 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: Phone: (316) 640-9072

Proposed
Plugging
Method:

Set 50 ft cement plug on bottom. Set 50 ft plug at 800 ft (Douglas). Cement from 250 ft to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2014 2:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 2085' pumped 10 sxs cement, pulled tubing to 800' pumped 10 sxs cement, pulled tubing to 250' pumped 50 sxs cement, gel spacers between cement plugs.

RECEIVED

MAY 19 2014

KCC Chanute Dist. #3

MH

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Doffner

(TECHNICIAN)

KCC WICHITA

MAY 21 2014

RECEIVED

Form CP-2/3