

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24203-00-00
Spot: N2SWNWSE Sec/Twnshp/Rge: 16-9S-16W
1770 feet from S Section Line, 2310 feet from E Section Line
Lease Name: J.C. Well #: 1-16
County: ROOKS Total Vertical Depth: 3695 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	641		270 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/24/2014 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 04/24/2014 8:30 AM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @3519 w/50 sx
2nd plug @1340 w/25 sx
3rd plug @820 w/100 sx
4th plug @695 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

KCC WICHITA
APR 30 2014
RECEIVED

District: 04

Signed Chris Neeley
(TECHNICIAN)

CM

APR 25 2014