

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-013-19019-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 3-1S-15E
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: LIVENGOOD Well #: 2
County: BROWN Total Vertical Depth: 2658 feet

Operator License No.: 33397
Op Name: RUNNING FOXES PETROLEUM INC.
Address: 6855 SHAVANA ST, STE 400
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2600		100 SX
SURF	8.625	200		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2014 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: CHAD COUNTS Company: RUNNING FOXES PETROLEUM, IN Phone: (720) 889-0510

Proposed Plugging Method: Perf 2 zones, set bridge plugs. Plug back to surface from 250

Plugging Proposal Received By: STEVE KORF Witness Type: NONE
Date/Time Plugging Completed: 03/26/2014 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PERFORATED THE CASING AT 1400' AND 250'. RAN TUBING DOWN TO 2600' AND PUMPED 20 SACKS OF CEMENT. PULLED THE TUBING UP TO 1400' AND PUMPED 20 SACKS OF CEMENT. PULLED THE TUBING UP TO 250' AND CIRCULATED 560 SACKS OF CEMENT TO THE SURFACE.

Perfs:

Top	Bot	Thru	Comments
1400	1401		
250	251		

RECEIVED
MAY 01 2014
KCC Chanute Dist #3
TH

Remarks:

Plugged through: TBG

KCC WICHITA

MAY 05 2014

District: 03

Signed

Taylor C. Herman
6/11/14

(TECHNICIAN)

RECEIVED