

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21550-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 17-23S-9W
900 feet from S Section Line, 400 feet from E Section Line
Lease Name: GEIST Well #: 1
County: RENO Total Vertical Depth: 3927 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN, STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3833	2590	175 SX
SURF	8.625	276		200 SX
T1	2.375	3636		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/10/2014 4:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: _____

Proposed Plugging Method: As per KCC Rules and Regulations

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/10/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3622' CAPPED WITH 2SXS CEMENT ON TOP, 11-20-13 LOG TECH OF KS. DROPPED SAND TO 3400' CAPPED WITH 5 SXS CEMENT. CUT CASING PIPE OFF @ 2590' PULLED CASING TO 1352' SPOTTED 35 SXS CEMENT. PULLED CASING TO 898' SPOTTED 35 SXS CEMENT. PULLED CASING TO 328' CIRCULATED TO SURFACE WITH 150 SXS CEMENT. 4/10/14 TAGGED TOC @ 12' - 4 SXS TO CLOSE.

Perfs:

Top	Bot	Thru	Comments
3663	3694		

KCC WICHITA
APR 29 2014
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET, DO NOT HAVE TICKET BOOK. LOST LEASE, DENIED TA.

Plugged through: CSG

District: 02

Signed BJ Hope
6/09/14
(TECHNICIAN)