

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21439-00-00  
Spot: S2N2N2SW Sec/Twnshp/Rge: 1-12S-25W  
2220 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: SCHIMKOWITSCH C Well #: 4-1  
County: TREGO Total Vertical Depth: 4180 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 4178       |             | 200 SX   |
| SURF   | 8.625 | 237        |             | 200 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2014 8:30 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: THOMAS ATKINS Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 623-8120

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV Tool at 2153' w/400 sx cement.  
Perforations: 4070' - 4080'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/07/2014 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4100' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 2700' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off w/40 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 100 psi.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4070 | 4080 |      |          |

Remarks: ALLIED CEMENT TICKET # 55255

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)  
6/11/14

CM

MAY 08 2014

KCC WICHITA

Form CP-2/3

MAY 15 2014

RECEIVED