

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21528-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 27-23S-17W
1372 feet from N Section Line, 455 feet from E Section Line
Lease Name: STUDE Well #: 1
County: PAWNEE Total Vertical Depth: 4590 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
PROD	5.5	4575	2350	WITH 175 SX CMT
SURF	8.625	270		WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/29/2014 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4150' WITH 2 SX CMT. PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2014 2:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4150' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1118' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 301' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4200	4218		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
6/09/14 (TECHNICIAN)

RECEIVED
MAY - 5 2014
KCC DODGE CITY

KCC WICHITA
MAY 12 2014
RECEIVED

Form CP-2/3

RAM