

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23773-00-01
Spot: NWNWNWSE Sec/Twnshp/Rge: 9-34S-8E
2372 feet from S Section Line, 2383 feet from E Section Line
Lease Name: JARBOE A OWWO Well #: 1
County: COWLEY Total Vertical Depth: 2422 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 2421 | | 255 SX |
| SURF | 8.625 | 174 | | 125 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2014 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 02/25/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 1858', DUMP BAILED 4 SXS CEMENT ON TOP. DUG OUT CELLER, CEMENT ON BACKSIDE OF 4 1/2" @ SURFACE. RIH W/TBG @ 550', GRESSEL MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. P&A COMPLETE 2-25-2014. CEMENT CIRCUALTED. CEMENT TICKET #40791.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2371 | 2385 | CSG | |
| 2059 | 2062 | CSG | |
| 2015 | 2020 | CSG | |
| 1917 | 1922 | CSG | |

KCC WICHITA

Remarks:

MAY 06 2014

Plugged through: TBG

RECEIVED

District: 02

Signed DUANE KRUEGER
6/12/14 (TECHNICIAN)