

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24344-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 21-20S-23W
1500 feet from S Section Line, 1062 feet from E Section Line
Lease Name: PETERSILIE VN Well #: 1-21
County: NESS Total Vertical Depth: 4410 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1553		
PROD	5.5	4401	0	WITH 225 SX CMT
SURF	8.625	207		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2014 1:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2014 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4400' & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1510' & PUMP 170 SX CMT. CMT CIRCULATED. PULL TBG & TOP OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4396	4403		

KCC WICHITA

MAY 20 2014

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier
6/09/14

(TECHNICIAN)

RECEIVED

MAY 13 2014

KCC DODGE CITY

Form CP-2/3