

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-00193-00-01
Spot: NENWNE Sec/Twnshp/Rge: 30-22S-3W
330 feet from N Section Line, 1650 feet from E Section Line
Lease Name: SCHMIDT K Well #: 1
County: HARVEY Total Vertical Depth: 2710 feet

Operator License No.: 6804
Op Name: LACHENMAYR OIL LLC
Address: PO BOX 526
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2600	1830	200
PROD	4.5	2710		25 SX
SURF	20	270		200 SX
T1	2.375	2615		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2014 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOHN LACHENMAYR Company: _____ Phone: (316) 284-1991

Proposed Plugging Method: Per KCC Instructions There are multiple strings of casing in this well 20" 270', 15.5 490', 13.375 1648', 10.25 2275', 7" liner from 2434-2520 feet

Plugging Proposal Received By: HUNTER CLARK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/25/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2560' - INSIDE 5.5" THAT HAS 4.5" ON BOTTOM. PULLED 1830' FEET OF 5.5" CASING. TRIED TO PULL 8.625 GOT NO STRETCH, DUG DOWN AND FOUND THE 20", CUT OFF COULD NOT FIND REST OF PIPE STRINGS LISTED ON CP-1, MOST LIKELY PULLED PREVIOUSLY. LOADED HOLE WITH FRESH WATER @ 557' SHOT 4 SHOTS INTO 8.625 CASING, UNLOADED WATER IN 30 SECONDS, RAN TUBING INTO 550' SPOTTED 100 SXS COMMON WITH 3% CC, BUTTONED UP LET STAND OVERNITE. 3/21/14 TAGGED TOC @ 435'. PERFORATED 8.625 WITH 4 SHOTS @ 315, MUD CAME IN COULD NOT GET PAST 315' WITH WIRELINE AFTER SHOOTING CASING, RAN TUBING INTO 315' PUMPED 575 SXS OF CEMENT DID NOT CIRCULATE. 3/24/14 TAGGED CEMENT AT 60' INSIDE 8.625, TAGGED CEMENT @ 28' BETWEEN 20" AND 8.625. FILLED WITH 55 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2620	2624		

Remarks: QUALITY WELL SERVICE SUPPLIED CEMENT FOR THIS PLUGGING.

Plugged through: TBG


KCC WICHITA

APR 29 2014

RECEIVED

District: 02

Signed



(TECHNICIAN)