

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19225-00-01
Spot: SEWNNE Sec/Twnshp/Rge: 10-30S-4E
4436 feet from S Section Line, 2018 feet from E Section Line
Lease Name: DAVES UNIT Well #: 2
County: COWLEY Total Vertical Depth: 2801 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2801	308	80 SX
SURF	8.625	170		110 SX

Well Type: EOR UIC Docket No: E12366.2 Date/Time to Plug: 05/07/2014 8:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ROB WILLIAMS Company: STELBAR OIL CORPORATION Phone: (316) 641-0024

Proposed
Plugging
Method:

AS PER KCC RULES & REGS/ CIBP @ 2720 W/5 SXS PULL PIPE & CIRC 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/08/2014 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2592', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5 1/2" CASING @ 308', LAYED DOWN 5 1/2" CASING (10 JONTS). RIH W/TBG @ 300', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 124 SXS 60/40 POZMIX 4% GEL, 2% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5-8-2014 10:00 AM. CONSOLIDTED CEMENT TICKET #46331.

Perfs:

Top	Bot	Thru	Comments
2772	2787		

KCC WICHITA

Remarks:

Plugged through: TBG

MAY 15 2014

RECEIVED

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

✓ cc to VMC 6/16/14
✓ 6/11/14
JK