

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20443-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 11-25S-21W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SCHALLER (BELLAFONT LAN Well #: 4
County: FORD Total Vertical Depth: 4785 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4785	1450	WITH 220 SX CMT
SURF	8.625	471		WITH 220 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2014 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PUMP 25 SX CMT & 150# HULLS AT 4650'. BLOW COLLAR @ 1425'. ATTEMPT TO PULL. IF THEY CANNOT, SPOT 50 SX CMT. AFTER PULLING CASING, SPOT 50 SX CMT AT 500'. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2014 5:25 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS AT 4650' THROUGH TUBING. 1ST PLUG AT 1400' WITH 50 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 31' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4670	4676		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

KCC WICHITA
MAY 20 2014
RECEIVED

District: 01

Signed Daniel Sellers
6/09/14 (TECHNICIAN)

RECEIVED
MAY 12 2014
KCC DODGE CITY