

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-24390-00-00  
Spot: NENWSESW Sec/Twnshp/Rge: 31-31S-8E  
1004 feet from S Section Line, 8823 feet from E Section Line  
Lease Name: FISHER FAMILY TRUST Well #: 31-1  
County: COWLEY Total Vertical Depth: 2691 feet

Operator License No.: 33711  
Op Name: B-C STEEL, LLC  
Address: 1432 NIGHTHAWK RD  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2601		150 SX
SURF	8.625	450		135 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/14/2014 8:00 AM  
Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC  
Proposal Rcvd. from: ROGER ALTUS Company: RCCA WELL SERVICE Phone: (316) 648-5431

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 1928', 500' CIRC TO SURFACE

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/15/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 1928', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1200', LAYED DOWN 1200' (30 JOINTS 4 1/2" CASING. 5-14-2014, RIH W/TBG @ 507', RCCA ESTABLISHED CIRCULATION, MIXED & PUMPED 186 SXS CLASS A COMMON 1% CC TO SURFACE. CEMENT CIRCUALTED. 5-15-2014, TAGGED CEMENT @ 45', TOPPED WELL BACK TO SURFACE W/20 SXS CLASS A COMMON. P&A COMPLETE. NO TICKET #.

Perfs:

Top	Bot	Thru	Comments
1978	1988	CSG	

Remarks: COMPLIANCE

KCC WICHITA

Plugged through: TBG

JUN 02 2014

RECEIVED

District: 02

Signed

DUANE KRUEGER  
6/05/14 (TECHNICIAN)