

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20300-00-00
Spot: NESENE Sec/Twnshp/Rge: 10-35S-29W
1650 feet from N Section Line, 330 feet from E Section Line
Lease Name: ADAMS RANCH Well #: F-14
County: MEADE Total Vertical Depth: 4560 feet

Operator License No.: 34399
Op Name: QUANTUM RESOURCES MANAGEMEN
Address: 1401 MCKINNEY ST, STE 2400
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4350		WITH 2 SX CMT
PROD	4.5	4550	2430	WITH 250 SX CMT
SURF	8.625	1525		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2014 8:00 AM
Plug Co. License No.: 34396 Plug Co. Name: FREEPOINT PIPE AND SUPPLY INC.
Proposal Rcvd. from: DENNIS OAKLEY Company: FREEPOINT PIPE AND SUPPLY INC Phone: (405) 341-1913

Proposed Plugging Method: PLUG AT 1550' WITH 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 05/16/2014 9:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4350' WITH 2 SX CMT. 1ST PLUG AT 1575' WITH 80 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 34' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4430	4436		

Received
KANSAS CORPORATION COMMISSION

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL.

JUN 06 2014

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

MAY 30 2014

KCC DODGE CITY

Signed

Richard Lacey
(TECHNICIAN)

✓ 6/11/14

Form CP-2/3