

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20191-00-00
Spot: E2 Sec/Twnshp/Rge: 26-21S-32W
2640 feet from S Section Line, 1320 feet from E Section Line
Lease Name: LANDGRAF C Well #: 1-26
County: FINNEY Total Vertical Depth: 2806 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2805	0	WITH 500 SX CMT
SURF	8.625	380		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2014 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 135 SX CMT WITH 250# HULLS. DISPLACE TO 1300'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. RUN TBG. AND OR PERFORATE AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2014 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 90 SX CMT WITH 250# HULLS DOWN 4 1/2" CASING. DISPLACE TO 1300' WITH WATER & PRESSURE TO 700#. HOLDING. RUN CBL FROM 1300' TO 50'. TOC @ 80'. ALL USABLE WATER & FRESH WATER ZONES COVERED WITH CMT. RUN TBG TO 1306' & CIRCULATE CMT TO SURFACE WITH 85 SX CMT. TOOH W/TBG. TOP OFF WITH 10 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS & PRESSURE TO 500#.

Perfs:

Top	Bot	Thru	Comments
2724	2734		

Received
KANSAS CORPORATION COMMISSION
JUN 06 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED

Plugged through: TBG

District: 01

Signed

Ken Jehlik
6/10/14

(TECHNICIAN)

RECEIVED
MAY 22 2014
KCC DODGE CITY

Form CP-2/3