

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20925-00-00
Spot: NENENW Sec/Twnshp/Rge: 14-12S-21W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KOHL/COTTON Well #: 3
County: TREGO Total Vertical Depth: 4048 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4038		475 SX
SURF	8.625	226		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2014 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAN WEINHOLD Company: PROFESSIONAL PULLING SERVIC Phone: (785) 483-1599

Proposed Perforations unknown.
Plugging Shot perforations at 2250', 1775', 1025' and 230'.
Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2014 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3800'. Pumped 13 sx gel followed by 50 sx cement and 100 # hulls. Pulled tubing to 2242' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1050' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out. Tied on to casing and squeezed with 50 sx cement. Shut in with 200 psi. Tied on to backside and no cement was needed. Hole standing full.

Perfs:

Remarks: QUALITY CEMENT TICKET # 118

Plugged through: TBG

District: 04

Signed: 
(TECHNICIAN)

CM

MAY 08 2014

KCC WICHITA

Form CP-2/3

MAY 15 2014

RECEIVED