

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20658-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 18-17S-24W
1892 feet from N Section Line, 616 feet from E Section Line
Lease Name: SARGENT Well #: 1
County: NESS Total Vertical Depth: 4410 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4400	0	WITH 150 SX CMT
SURF	8.625	216		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2014 2:30 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 1900' & SPOT 50 SX CMT. PULL TBG TO 1350' & SPOT 60 SX CMT. TEST CASING. IF HOLDS, PERFORATE @ 1150' & PUMP 80 SX CMT OVER CASING VOLUME THEN 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/02/2014 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

5/1/14: RUN TBG TO 4315' & PUMPED 50 SX COMMON CMT & 200# HULLS. PULLED TBG TO 1900' & PUMPED 50 SX COMMON CMT W/3% CC. PULLED TBG TO 1300' & PUMPED 60 SX COMMON CMT W/3% CC. SDON. 5/2/14: PRESSURED CASING & HELD AT 500#. RUN IN & FOUND CMT AT 1020'. PERFORATE AT 1000' & PUMPED 175 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE WAS 600#. TIED ONTO BACKSIDE & PUMPED 150 SX CMT. PRESSURED TO 100#.

Perfs:

Top	Bot	Thru	Comments
4400	4410	OH	

KCC WICHITA
MAY 20 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA NEED CURRENT FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

MAY 15 2014

KCC DODGE CITY

Signed

Michael Maier
6/10/14

(TECHNICIAN)