

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24121-00-00
Spot: SWSENE Sec/Twnshp/Rge: 18-17S-24W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: SARGENT Well #: 5
County: NESS Total Vertical Depth: 4405 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1682		WITH 400 SX CMT
PROD	5.5	4398	0	WITH 200 SX CMT
SURF	8.625	280		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2014 12:30 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT. CIRCULATE CMT FROM 1700' TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2014 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4371' & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1705' & PUMP 185 SX CMT. CMT CIRCULATED. PULL TBG & TOP OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4398	4405	OH	

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.


MAY 20 2014

Plugged through: TBG

RECEIVED

District: 01

Signed


(TECHNICIAN)

RECEIVED

MAY - 9 2014

KCC DODGE CITY

Form CP-2/3

