

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20814-00-02
Spot: NESWSWNE Sec/Twnshp/Rge: 4-26S-36W
3150 feet from S Section Line, 2130 feet from E Section Line
Lease Name: LEE Well #: 5-4
County: KEARNY Total Vertical Depth: 5090 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1900		
CIBP		4918		
PROD	5.5	5090	0	WITH 250 SX CMT
SURF	8.625	1855		WITH 755 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2014 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4940' WITH 2 SX CMT. PLUG AT 1885' WITH 10-15 SX GEL & 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4918'. TWO ATTEMPTS TO DUMP CMT ON TOP OF PLUG WERE UNSUCCESSFUL. CIBP @ 1900'. TEST CASING TO 700#. HOLDING. PERFORATE 2 HOLES AT 1880'. SPOT 50 SX CMT HALF IN & HALF OUT OF PERFS AT 1880' @ 600#. FULL CIRCULATION. PERFORATE 2 HOLES @ 750'. CIRCULATE CMT TO SURFACE USING 200 SX CMT, LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4990	4998		

KCC WICHITA
MAY 27 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIZ 4% GEL BY ALLIED.

Plugged through: CSG


District: 01

RECEIVED

MAY 21 2014

KCC DODGE CITY

Signed



(TECHNICIAN)

Form CP-2/3